# CITY OF WEST DES MOINES PLAN AND ZONING COMMISSION COMMUNICATION

Meeting Date: February 24, 2020

Item: Wirtz Commercial Park Plat 6/Kindercare Learning Center, 865 S. 51st

Street – Approve Preliminary Plat to Subdivide Property into Two Commercial Lots and One Street Lot and Approve Site Plan to Construct a 12,000 sq. ft. Childcare Building – EIG14T Development–

PP-004556-2019/SP-004553-2019

Requested Action: Recommend Approval of a Preliminary Plat and Approval of a Site Plan

Case Advisor: Kara Tragesser, AICP

<u>Applicant's Request</u>: The applicant, EIG14T Development, with permission from the property owner, Hy-Vee, Inc., requests approval of a preliminary plat to subdivide property located at 865 S. 51<sup>st</sup> Street into two commercial lots and one street lot. Also requested is approval of a site plan to construct a 12,000 sq. ft. childcare center on Lot 1.

<u>History</u>: The property being platted is a replat of Lots 2 and 3 Wirtz Commercial Park Plat 1 originally platted in 2000. The property is located within the Wirtz Planned Unit Development and has an underlying zoning of Support Commercial. A childcare center is a Permitted Conditional Use in this zoning district; the Board of Adjustment approved the permitted conditional use permit on November 20, 2019. A vacation of a 30 foot buffer park along the south and west side of both lots was approved under public hearing by the City Council on December 16, 2019.

<u>City Council Subcommittee</u>: This item was presented to the Development & Planning City Council Subcommittee at their December 2, 2019 meeting, the Subcommittee supported the preliminary plat and site plan.

**<u>Staff Review and Comment:</u>** This request was distributed to other City departments and other agencies for their review and comment. There are no outstanding issues. Staff notes the following:

There is a condition of approval regarding the issuance of a building permit upon either the final plat being filed or a situation where the childcare center can be wholly constructed on Lot 2 of Wirtz Commercial Park Plat 1. Lot 2 Wirtz Commercial Park Plat 1 is a legal lot of record and could be developed without the replat that is occurring through the current review process. The intent of the applicant is to fulfill the process through a replat with a final plat proceeding to the City Council in the near future, however, staff wants to cover the contingency that the final plat is not approved before the applicant wishes to construct the childcare center. Staff presents that condition of approval to address that situation.

<u>Comprehensive Plan Consistency</u>: The project has been reviewed for consistency with the Comprehensive Plan. Based upon that review, a finding has been made that the proposed project is consistent with the Comprehensive Plan in that the project is consistent with all of the goals and policies of the Comprehensive Plan and the land use map of the Comprehensive Plan.

**Findings**: This proposed project was distributed to various city departments for review and comment. Based upon that review, the following findings have been made on the proposed project:

The proposed development and use is consistent with the West Des Moines Comprehensive Plan
in that the project has been reviewed for consistency with the Comprehensive Plan. Based upon
that review, a finding has been made that the proposed project is consistent with the
Comprehensive Plan in that the project is consistent with all the goals and policies of the
Comprehensive Plan.

- 2. The proposed development and use does assure compatibility of property uses within the zone and general area in that this project was reviewed by various City Departments for compliance with the Zoning Ordinance.
- 3. All applicable standards and conditions have been imposed which protects the public health, safety and welfare in that this project was reviewed by various City Departments and public agencies for compliance with the various state and local regulations. Based upon that review a finding is made that the project has been adequately conditioned to protect the health, welfare and safety of the community.
- 4. There is adequate on-site and off-site public infrastructure to support the proposed development in that this project was reviewed by various public agencies and City Departments and public utilities to ensure that either the petitioner will construct or the project has been conditioned to construct adequate public infrastructure to serve the development.
- 5. The proposed development and use has met the requirements contained in the City Code in that this project was reviewed by various City Departments and the project has complied with or has been conditioned to comply with all City Code requirements.
- The proposed development and use is in keeping with the scale and nature of the surrounding neighborhood in that the proposed project is consistent with the zoning designation and Comprehensive Plan which designates this site as suitable for development such as that proposed by this project.

Staff Recommendation and Conditions of Approval: Based upon the preceding review and a finding of consistency with the goals and policies of the Comprehensive Plan staff recommends the Plan and Zoning Commission adopt a resolution recommending the City Council approve the Wirtz Commercial Park Plat 6 and the Site Plan for Kindercare Learning Center, subject to the applicant meeting all City Code requirements and the following:

- 1. That remaining comments on the storm water pollution prevention plan be provided prior to the issuance of a building permit for either lot.
- 2. Provide screening information for the ground mounted mechanical units prior to the issuance of a building permit for the childcare center building.
- 3. That no building permit be issued for the childcare center building until either the final plat for Wirtz Commercial Park Plat 1 has been approved and filed with the county or the site plan is revised to show all site plan improvements meet codes and regulations to be constructed on Lot 2 Wirtz Commercial Park Plat 1.
- 4. That the balance of the traffic study fee be paid prior to issuance of a building permit.

Property Owner: Hy-Vee, Inc.

5820 Westown Parkway West Des Moines IA 50266

Pete Hosch

Applicant(s): EIG14T Development

3221 W. Big Beaver Road, Suite 111

Troy MIC 48084 Samantha Coponen

Applicant's Representatives:

ISG

7900 International Drive Suite 550

Minneapolis MN 55425

Ryan Anderson

#### **ATTACHMENTS:**

Plan and Zoning Commission Resolution

- Conditions of Approval Location Map

Attachment A Exhibit A
Attachment B Attachment C Attachment D Attachment E -Preliminary Plat Site Plan

**Building Elevations** 

#### RESOLUTION NO. PZC - 20-007

# A RESOLUTION OF THE PLAN AND ZONING COMMISSION OF THE CITY OF WEST DES MOINES, IOWA, RECOMMENDING TO THE CITY COUNCIL THAT IT APPROVE THE WIRTZ COMMERCIAL PARK PLAT 6 AND SITE PLAN FOR KINDERCARE LEARNIG CENTER AT 865 S. 51<sup>ST</sup> STREET

**WHEREAS,** pursuant to the provisions of Title 9, Chapter 1 et seq, of the West Des Moines Municipal Code, the applicant, ElG14T Development, request approval of a preliminary plat to subdivide the property at 865 S. 51st Street into two lots for commercial development and approval of a site plan to construct a 12,000 sq. ft. child care center; and

**WHEREAS,** studies and investigations were made and staff reports and recommendations were submitted which are made a part of this record and herein incorporated by reference; and

WHEREAS, on February 24, 2020, this Commission held a duly-noticed meeting to consider the Preliminary Plat and Site Plan;

NOW, THEREFORE, THE PLAN AND ZONING COMMISSION OF THE CITY OF WEST DES MOINES DOES RESOLVE AS FOLLOWS:

<u>SECTION 1</u>. The findings, for approval, in the staff report, dated February 24, 2020, or as amended orally at the Plan and Zoning Commission hearing of February 24, 2020, are adopted.

<u>SECTION 2</u>. The Wirtz Commercial Park Plat 6 preliminary plat (PP-004556-2019) and the site plan (SP-004553-2019) for Kindercare Learning Center are recommended to the City Council for approval, subject to compliance with all the conditions in the staff report, dated February 24, 2020, including conditions added at the meeting, and attached hereto as Exhibit "A". Violation of any such conditions shall be grounds for revocation of the permit, as well as any other remedy which is available to the City.

PASSED AND ADOPTED on February 24, 2020.

Erica Andersen, Chair
Plan and Zoning Commission

ATTEST:

Recording Secretary


I HEREBY CERTIFY that the foregoing resolution was duly adopted by the Plan and Zoning Commission of the City of West Des Moines, Iowa, at a regular meeting held on February 24, 2020, by the following vote:


AYES:
NAYS:
ABSTENTIONS:
ABSENT:

ATTEST:

# Exhibit A Conditions of Approval

- 1. That remaining comments on the storm water pollution prevention plan be provided prior to the issuance of a building permit for either lot.
- 2. Provide screening information for the ground mounted mechanical units prior to the issuance of a building permit for the childcare center building.
- 3. That no building permit be issued for the childcare center building until either the final plat for Wirtz Commercial Park Plat 1 has been approved and filed with the county or the site plan is revised to show all site plan improvements meet codes and regulations to be constructed on Lot 2 Wirtz Commercial Park Plat 1.
- 4. That the balance of the traffic study fee be paid prior to issuance of a building permit.






# ATTACHMENT C



## VICINITY MAP



SE 1/4 SEC. 18, TWP. 78, RGE. 25 Polk County, Iowa

HEREBY CERTIFY THAT THIS LAND SURVEYING DOCUMENT WAS PREPARED AND THE RELATED SURVEY WORK WAS PERFORMED BY ME OR UNDER MY DIRECT PERSONAL SUPERMISSION AND THAT IAM A DULY LICENSED LAND THE STATE OF IOWA.

Tom W.G. Edgerton License Number 14199 My license renewal date is 12-31-2021 Pages or sheets covered by this seal: 1

THIS DOCUMENT IS THE PROPERTY OF LAS GROUP INC. AND MAY NOT BE USED, COPIED OR DUPLICATE WITHOUT PRIOR WRITTEN CONSENT.

SURVEYOR:

515-243-9143

SCALE IN FEET

**LEGEND** 

508 East Locust Street

## **KINDERCARE LEARNING CENTERS**

Lots 2 and 3, Wirtz Commercial Park Plat No. 2 City of West Des Moines, Polk County, IA

	REVIS	ION SCHEDULE	
DATE		DESCRIPTION	BY
8/21/19			KH
01/07/20	City Comment	s	JW
02/17/20	City Comment	8	ARA
02/20/20	City Comment	s	JW
PROJECT		19-23523 23523 PPLAT	
DRAWN	3Y	JW	
DESIGNE		-	
REVIEWS	D BY	TWGE	
ORIGINA	L ISSUE DATE		
CLIENT F	ROJECT NO.	SP-004553-2019	
TITLE			

**PRELIMINARY PLAT** 

Utility Marker

Coniferous Tree


Utility Hand Hote

Manhole/Catch Basin

 $\odot$ 

 $\cap$ 

OF



- ALL WORK SHALL CONFORM TO THE CONTRACT DOCUMENTS, WHICH INCLUDE, BUT ARE NOT LIMITED TO, THE OWNER - CONTRACTOR AGREEMENT. TH PROJECT MANUAL (WHICH INCLUDES GENERAL SUPPLEMENTARY CONDITIONS AND SPECIFICATIONS), DRAWINGS OF ALL DISCIPLINES AND ALL ADDENDA, MODIFICATIONS AND CLASSIFICATIONS AND CLASSI
- CONTRACT DOCUMENTS SHALL BE ISSUED TO ALL SUBCONTRACTORS BY THE NERAL CONTRACTOR IN COMPLETE SETS IN ORDER TO ACHIEVE THE FULL EXTENT AND COMPLETE COORDINATION OF ALL WORK
- WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS NOTIFY ARCHITECT/ENGINEER OF ANY DISCREPANCIES OR CONDITIONS REQUIR INFORMATION OR CLARIFICATION BEFORE PROCEEDING WITH THE WORK.
- 4. FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS, NOTIFY ARCHITECT/ENGINEER OF ANY DISCREPANCIES OR CONDITIONS REQUIRING INFORMATION OR CLARIFICATION BEFORE PROCEEDING WITH THE WORK.
- DETAILS SHOWN ARE INTENDED TO BE INDICATIVE OF THE PROFILES AND TYPE OF DETAILING REQUIRED THROUGHOUT THE WORK, DETAILS NOT SHOWN ARE SIMILAR IN CHARACTER TO DETAILS SHOWN, WHERE SPECIFIC DIMENSIONS DETAILS OR DESIGN INTENT CANNOT BE DETERMINED, NOTIFY ARCHITECT/ENGINEER BEFORE PROCEEDING WITH THE WORK
- 8. ALL MANUFACTURED ARTICLES, MATERIALS AND EQUIPMENT SHALL BE APPLIED, INSTALLED, CONNECTED, ERECTED, CLEANED AND CONDITIONED ACCORDING TO MANUFACTURERS' INSTRUCTIONS. IN CASE OF DISCREPANCIES BETWEEN MANUFACTURERS' INSTRUCTIONS AND THE CONTRACT DOCUMENTS, NOTIFY ARCHITECT/ENGINEER BEFORE PROCEEDING WITH THE WORK.
- 7. ALL DISSIMILAR METALS SHALL BE EFFECTIVELY ISOLATED FROM EACH OTHER TO AVOID GALVANIC CORROSION.
- THE LOCATION AND TYPE OF ALL INPLACE UTILITIES SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION ONLY AND ARE ACCURATE AND COMPLETE TO THE BEST OF THE KNOWLEDGE OF I & S GROUP, INC. (ISG), NO WARRANTY OR GUARANTEE IS IMPLIED. THE CONTRACTOR SHALL VERIFY THE SIZES, LOCATIONS AND ELEVATIONS OF ALL INPLACE UTILITIES PRIOR TO CONSTRUCTION.
  CONTRACTOR SHALL IMMEDIATELY NOTIFY ENGINEER OF ANY DISCREPANCIES OR VARIATIONS FROM PLAN.
- THE CONTRACTOR IS TO CONTACT "IOWA ONE CALL" FOR UTILITY LOCATIONS MINIMUM 2 BUSINESS DAYS PRIOR TO ANY EXCAVATION / CONSTRUCTION (1-800-292-8989).
- 10. AT LEAST ONE WEEK PRIOR TO ANY CONSTRUCTION WITHIN PUBLIC R.O.W.PASEMENTS AND/OR ANY CONNECTION TO PUBLIC SEWERS AND STREETS, THE CONTRACT HE WOM ENGINEERING SERVICES BEN MCALISTER 222-3475 TO OBTAIN APPLICABLE CITY PERMITS THAT MAY BE NECESSARY, IT IS IMPORTANT TO NOTE CITY APPROVAL OF THIS PLAN IS SUBJECT TO THE APPLICANT OBTAINING ALL NECESSARY EASEMENTS/AGREEMENTS AND APPLICABLE PERMITS.
- 11. APPLICANT SHOULD BE MADE AWARE ANY SIGNING, STRIPING OR OTHER TRAFFIC CONTROL DEVICES ON THE DRIVEWAY APPROACHES TO PUBLIC STREETS SHOULD CONFORM TO THE (MUTCD) MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (FEDERAL HIGHWAY ADMINISTRATION, 2009 EDITION). A NOTE SHALL BE PROVIDED ON THE SITE PLAN INDICATING THIS,

#### **SPECIFICATIONS REFERENCE**

ALL CONSTRUCTION SHALL COMPLY WITH THE PROJECT SPECIFICATIONS, THE CITY OF WEST DES MOINES REQUIREMENTS, THE WEST DES MOINES WATER WORKS (WDMWN), SPECIFICATIONS, THE 2019 EDITION OF THE STATEWIDE URBAN DESIGN AND SPECIFICATIONS (SUDAS) FOR CONSTRUCTION, AND CURRENT VERSION OF THE PLUMBING CODE OF IOWA UNLESS DIRECTED OTHERWISE.

#### PROJECT DATUM

HORIZONTAL COORDINATES HAVE BEEN REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (NAD83), SOUTH ZONE, ON THE IOWA STATE PLANE COORDINATE SYSTEM, IN U.S. SURVEY FEET.
ELEVATIONS HAVE BEEN REFERENCED TO THE CITY OF WEST DES MOINES DATUM. RTX GPS METHODS WERE USED TO ESTABLISH HORIZONTAL AND VERTICAL COORDINATES FOR THIS PROJECT.

THE BENCHMARKS USED FOR THE BASIS OF THE ELEVATIONS SHOWN HEREON ARE CITY OF WEST DES MOINES BENCHMARK NUMBER 004, ELEVATION = 119.81. FOUND AT S. 35TH STREET AT NORTH ENTRANCE TO SOUTHWOODS PARK. CITY OF WEST DES MOINES BENCHMARK NUMBER 127. ELEVATION = 119.46. FOUND AT SOUTHWEST CORNER OF EP TRUE PARKWAY AND S. 41ST STREET.

#### **TOPOGRAPHIC SURVEY**

THIS PROJECT'S TOPOGRAPHIC SURVEY CONSISTS OF DATA COLLECTED IN

B.M. ELEVATION=198.85

#### B.M. ELEVATION = 201.73

YELLOW CAP 16747 - SW CORNER LOT WIRTZ COMMERCIAL PARK PLAT NO. 2



**LOCATION MAP** 



# KINDERCARE

# **WEST DES MOINES**

# EIGHT

#### LEGEND

PROJECT MANAGER: RYAN ANDERSON 7900 INTERNATIONAL DRIVE, SUITE 550 **MINNEAPOLIS, MN 55425** 

PHONE: 952-426-0699

PROPERTY OWNER: REED FENTON 814 ACQUISITIONS, LLC 3221 W. BIG BEAVER ROAD, SUITE 111 TROY, MI 48084 PHONE: 248-817-1691

APPLICANT: **SAMANTHA COPONEN EIG14T DEVELOPMENT** 3221 W. BIG BEAVER ROAD, SUITE 111 TROY, MI 48084 PHONE: 248-817-1691

PROJECT ADDRESS / LOCATION:

865 S. 51ST ST (PIN 320.04947.602.001)

WIRTZ COMMERCIAL PARK PLAT NO. 6, LOT 1, OUTLOT A, AND STREET LOT A

**SECTION 18, T-78N, R-25W** WALNUT TWP, POLK COUNTY

**WEST DES MOINES, IOWA** 

SITE SUMMARY							
ZONING / EXISTING LAND USE:		ORT COMMERCIAL (PE PREHENSIVE PLAN)	R CITY OF WEST				
EXISTING SITE/LOT AREA:	147,000 SQ. FT / 3.	37 AC.					
EXISTING IMPERVIOUS AREA:	0 SQ. FT / 0 AC. (0	6)					
ZONING / PROPOSED LAND USE:	PUD-33, PERMITTE SERVICES	D CONDITIONAL USE,	SIC 835 CHILD CARE				
SITE AREA / LOT 1	79,427 SQ. FT / 1.8	2 AC.					
LOT 1 IMPERVIOUS AREA:	46,640 SQ. FT / 1.0	7 AC. (58.72%) (REQUIS	RED 75% MAXIMUM)				
LOT 1 GREENSPACE PROVIDED:	32,767 SQ. FT / 0.7	5 AC. (41.28%) (REQUIF	RED 25% MINIMUM)				
SIGN REQUIREMENTS							
MAXIMUM HEIGHT:	5'-0"						
MONUMENT SIGN AREA:	35 SQ. FT						
SETBACK:	10'-0"						
TOTAL WALL SIGN AREA:	168 SQ. FT						
WALL SIGN LETTER HEIGHT:	6'-0"						
PARKING REC	UIREMEN	TS (PER CI	TY CODE)				
TYPE	UNIT / AREA	STALLS REQUIRED	STALLS PROVIDED				
9' X 19' (17' IF GREEN SPACE ABUTS STALL)		54	57				
	TOTAL:		57				

SETBACKS

BUILDING

60'-0"

0.0

PROVIDED

46"-10"

PARKING

15-0"

0'-0"

**CIVIL SHEET SET** 

COVER SHEET

DEMO PLAN

SITE PLAN

EXISTING CONDITION

SITE UTILITY PLAN

GRADING PLAN

PLANTING PLAN

RESTORATION PLAI

PHOTOMETRIC PLAN

SITE DETAILS

SITE DETAILS

SITE DETAILS

SITE DETAILS

SITE DETAILS

FIRST FLOOR PLAN

EXTERIOR ELEVATIONS

ROOF PLAN

FINISH BOARD

PLANTING SCHEDULE NOTES & DETAILS

FIRE TRUCK ACCESS AND HYDRANT COVERAGE PLAN TEMPORARY EROSION AND SEDIMENT CONTROL PLAN EROSION & SEDIMENT CONTROL NOTES AND DETAILS

Sheet Number

C100

C200

C300

C400

C500

C600

C700

C701

C702

C800

C810

C811

C812

C813

AE1-100a

AE1-300a

AE2-001a

FRONT YARD

SIDE YARD

REAR YARD

# EIGH

ATTACHMENT D

ONSTRUCTIO

0 Ľ

NOT

RELIMINARY

<u>Δ</u>

CTION

CONSTRU

OR

<u>L</u>

0

Ž

ELIMINARY

 $\mathbf{C}$ 

**T** 



1-800-292-8989

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT


**KINDERCARE** 


**WEST DES MOINES** 


WEST	DES MOI	NES	1			
	IS	SSUE SCHEDULE				
DATE		DESCRIPTION	BY			
11/04/19	CLIENT RE	VIEW SET	ARA			
11/13/19	CITY SITE	PLAN SUBMITTAL #1	ARA			
01/13/20	CITY SITE	PLAN SUBMITTAL #2	ARA			
02/17/20	CITY SITE	CITY SITE PLAN SUBMITTAL #3				
	RE	VISION SCHEDULE	-			
DATE		DESCRIPTION	B			
PROJEC	T NO.	19-23523				
FILE NAM	ΛE	23523 CO-DETAILS				
DRAWN	BY	ARA				
DESIGNE	D BY	ARA/RJA				
REVIEW	ED BY	RJA/ART				
	L IOCUE DA	TE ()				
ORIGINA	T ISSUE DA	15				


TITLE


**COVER SHEET** 











CONTACT BUILDING INSPECTION (515-222-3630) A MINIMUM OF 24 HOURS IN ADVANCE FOR PRIVATE UTIL!

ALL PROPOSED UTILITIES INSTALLED BY THIS PROJECT SHALL BE PRIVATE

ALL CONNECTIONS TO PUBLIC SEWER SHALL BE CORE DRILLED,

REFERENCE SUDAS SPECIFICATIONS, FIGURE WM-201, FOR VALVING AND PIPE MATERIAL AT HYDRANT TEE

ALL CONSTRUCTION WITHIN PUBLIC RIGHT OF WAY/EASEMENTS, AND/OR ANY CONNECTION TO PUBLIC SEWERS AND STREETS, SHALL COMPLY WITH THE WEST DES MOINES STANDARD CONSTRUCTION SPECIFICATIONS FOR SUBDIVISIONS, DSM METRO DESIGN STANDARDS AND WOM ADDENIBUMS.

WATERMAIN SCHEDULE									
PIPE TYPE	START STATION	END STATION	** PIPE LENGTH (FT)	PIPE SIZE (IN)					
8in PVC C900	0+04.96	0+08.52	4	8					
8in PVC C900	0+09.52	1+03,67	94	8					
6in PVC C900	1+04.29	1+04.29	2	6					
6in PVC C900	1+04.29	1+04,29	15	6					
Bin PVC C900	1+04,70	1+70.02	65	8					
Bin PVC C900	1+70.02	1+97.02	27	8					
4in C900	1+95.56	1+97,56	2	4					
4in C900	1+95.56	1+95.57	13	4					
Bin PVC C900	1+97,55	1+97.57	12	8					
Sin PVC C900	1+97.56	1+97.56	23	6					
6in PVC C900	1+97.56	1+97.56	2	6					
6in PVC C900	1+97.57	1+97.56	10	6					
8in PVC C900	1+97.57	1+97,56	3	8					

WATERMAIN FITTING SCHEDULE						
ALIGNMENT	TYPE	STATION				
23523 WATERMAIN ALIGNMENT	8x6 Reducer	1+98				
23523 WATERMAIN ALIGNMENT	8x6 Tee	1+04				
23523 WATERMAIN ALIGNMENT	8x8 Tee	1+98				

VALVE SC	HEDULE	Ē
ALIGNMENT	STATION	NOTES
23523 WATERMAIN ALIGNMENT	1+98	6in Gate Valve
23523 WATERMAIN ALIGNMENT	1+98	Hydrant 6'-0"
23523 WATERMAIN ALIGNMENT	1+98	Bin Gale Valve
23523 WATERMAIN ALIGNMENT	1+98	6in Gate Valve
23523 WATERMAIN ALIGNMENT	1+04	Hydrant 6'-0"
23523 WATERMAIN ALIGNMENT	1+04	6in Gate Valve
23523 WATERMAIN ALIGNMENT	0+09	Bin Gate Valve

		SA	ANITARY	SEWERI	PIPE	SCHEDU	LE				STORM DRA	IN APRON S	CHEDULE
PIPE NO.	DRAIN FROM	INLET ELEVATION	DRAIN TO	OUTLET	PIPE SIZE	MATERIAL	PIPE	PIPE GRADE	PIPE LENGTH (FT)	APRON NO.	APRON SIZE (in)	APRON MATERIAL	INVERT ELEVATION
SP-1	CO-1	183.37				77.00		_		FES-1	15	RC	191.74
SP-1	00-1	183,37	EX 6" STUB	182,90	6"	PVC	SDR-40	1.00%	47	FES-2	18	RC	192,25
SP-2	CO-2	190,89	CO-1	183.37	6"	PVC	SCH-40	8.00%	94	TEO-2	10	NO.	182.20
SP-3	BUILDING	191,29	CO-2	190.89	6"	PVC	SCH-40	8.00%	5	FES-3	12	RC	192.50
0, 0	DOILDING	151,220	002	130,03		110	GUITHU	0.00 %		FES-4	12	RC	192,50

R=196 61

l=191.68

SERVICE TO EXISTING STUB. CONTRACTOR TO VERIFY

SIZE, DEPTH, AND LOCATION.

- TAP WATER SERVICE TO

WATERMAIN (BY WDMWW)

l= 182.90

FES-1

R=193.30

R=196.49 i=192.28

R=197.91 I=192.56

FES-2

R=196.26

I=191.85

R=198.03

I=183.37

4" PERFORATED SUBDRAIN, TYP.

(SEE C810 SITE DETAILS)

P-2 (18\*)-

P-3 (12")

R=194.10

SANITARY SEWER STRUCTURE SCHEDULE								
STRUCTURE NO.	STRUCTURE TYPE	STRUCTURE SIZE (in)	STRUCTURE MATERIAL	CASTING	TOP OF CASTING ELEVATION	INVERT ELEVATION	PIPE NO.	
CO-1	CLEANOUT	6 Ø	PVC	SOLID	198.03	183.37	SP-1	
CO-2	CLEANOUT	60	PVC	SOLID	200.36	190.87	SP-2	

STRUCTURE NO.	STRUCTURE TYPE	STRUCTURE SIZE (In)	STRUCTURE MATERIAL	CASTING	* TOP OF CASTING ELEVATION	INVERT ELEVATION	OUTLET PIPE
A-1	SW-501	36 x 24	RC	SW-603 TYPE R	196,26	191.85	P-1
A-1A	SW-401	48 Ø	RC	SW-602 TYPE E	196,61	191.68	P-1A
A-2	SW-501	36 x 24	RC	SW-603 TYPE R	198.49	192.28	P-2
E-A	SW-501	36 x 24	RC	SW-603 TYPE R	197.91	192.56	P-3
A-4	SW-501	36 x 24	RC	SW-603 TYPE R	199.29	193.04	P-4
A-6	SW-401	48 Ø	RC	SW-602 TYPE E	199.87	193.50	P-5
A-6	SW-502	48 Ø	RC	SW-604 TYPE 3A	199,45	194,29	P-6
A.7	cm.sno	49.00	PC PC	SW SM TVDE 2A	409.64	406.45	D.7

STORM DRAIN SCHEDULE

R=199.45

J=194.29

TURE DRAIN

R=198.51

J=195.15

4" PERFORATED TURF DRAIN

MATERIAL GRADE LENGTH (FT)

0.30%

0.30%

5.85%

0.50%

132

HDPE 0.30%

HDPE

HDPE

HOPE

PROPOSED INGRESS/EGRESS

FROM

A-1A

FES-1

A-2

A-5

BUILDING

NO.

P-1

P-1A

P-18

P-2

P-4

P-5

P-8

EASEMENT

STORM DRAIN PIPE SCHEDULE

DRAIN OUTLET PIPE

192.25

191.57

192.45

12

192.88

193.16

192.50

193.70

195.15 A-6 194.39 12 HDPE 0.58%

194.00 FES-4 192.50 12 HDPE 7.13%

ELEVATION TO ELEVATION SIZE (IN)

FES-2

EX-ST1

A-2

FES-3

192.78 A-1

192.35

191.68

193.06

193.60

R=199.87

I=193,50

HL.

R=200.36

j=190.87

SP-3 (6"

6" PVC ROOF DRAIN, TYP.

6\* SANITARY SERVICE TO 5' FROM THE — BUILDING, CONNECTION INTO THE BUILDING BY MECHANICAL CONTRACTOR I=191,76

SINGLE STORY BUILDING

DAY CARE FACILITY

11.990 SF

FFE = 200.5

6" PVC ROOF DRAIN, TYP.

GAS, ELECTRIC AND PHONE SERVICE TO 5' FROM THE

BUILDING, CONNECTION INTO THE BUILDING BY

(SEE ARCH)

(SEE ARCH)

R=194.93

R=193.78

6" PVC ROOF DRAIN, TYP.

6" PVC ROOF DRAIN, TYP. (SEE ARCH)

- PROPOSED 24'

INGRESS/EGRESS EASEMENT

(SEE ARCH)

1,000 GAL, GREASE

INTERCEPTOR

40

I=193.04

PROPOSED 10' PRIVATE

\* TOP OF CASTING FLEVATION ON CURB STYLE CATCH BASINS SIGNIFIES TOP BACK OF CURB ELEVATION

STUB 8" PVC C900 WATER SERVICE 10' PAST -

PROPOSED HYDRANT FOR FUTURE WATER MAIN STUB

CURB (WITH 8"X6" WATER REDUCER)



N

PROJECT


**KINDERCARE** 


	ISSUE SCHEDULE	
DATE	DESCRIPTION	E
11/04/19	CLIENT REVIEW SET	AR
11/13/19	CITY SITE PLAN SUBMITTAL #1	AR
01/13/20	CITY SITE PLAN SUBMITTAL #2	AR
02/17/20	CITY SITE PLAN SUBMITTAL #3	AR
	REVISION SCHEDULE	_
DATE	DESCRIPTION	8
		-

PROJECT NO.	19-23523
FILE NAME	23523 C3-SITE
DRAWN BY	ARA
DESIGNED BY	ARA/RJA
REVIEWED BY	RJA/ART
ORIGINAL ISSUE DATE	
CLIENT PROJECT NO	


TITLE

SITE UTILITY PLAN





CONSTRUCTION



CONSTRUCTION

PRELIMINARY NOT FOR

CONSTRUCTION

FOR

PRELIMINARY NOT

# EIGHT

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

### **KINDERCARE**

**WEST DES MOINES** 

WEST DES MOINES	
	ISSUE SCHEDULE
DATE	DESCRIPTION
11/04/19	CLIENT REVIEW SET
11/13/19	CITY SITE PLAN SUBMITTAL #1
01/13/20	CITY SITE PLAN SUBMITTAL #2
02/17/20	CITY SITE PLAN SUBMITTAL #3

	REVISION SCHEDULE
DATE	DESCRIPTION

PROJECT NO.	19-23523
FILE NAME	23523 C5-LAND
DRAWN BY	ARA
DÉSIGNED BY	ARA/RJA
REVIEWED BY	RJA/ART
ORIGINAL ISSUE DATE	-/-/-
CLIENT PROJECT NO.	

**RESTORATION PLAN** 

SCALE IN FEET

C701

	BLUEGRASS SOD SALT-TOLERANT, IRRIGATED	17,995 s
* * *	RAINGARDEN, SEED MIX	6,510 sf

SEED SUDAS TYPE 1 SEED MIX

16,750 sf




3" CLEAN EGG STONE MULCH 1,963 sf REFER TO NOTES


NOTE: QUANTITIES SHOWN IN LEGEND ARE FOR CONVENIENCE ONLY. CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL MATERIALS PER PLAN.

MUST BE MAINTAINED UNTIL FINAL SEEDING AND STABILIZATION MEASURES ARE IN PLACE AND APPROVED BY THE OWNER'S REPRESENTATIVE.

#### **RESTORATION NOTE:**

ALL AREAS DISTURBED BY UTILITY INSTALLATION AND CONSTRUCTION SHALL BE HYDROSEEDED WITH SEED MIX AS SPECIFIED.





 ALL PLANTS TO BE INSTALLED SO THAT THE TOP OF THE CROWN OF THE PLANT IS SLIGHTLY ABOVE FINISH GRADE 3"

- CUT AND REMOVE AT MINIMUM THE TOP HALF OF WIRE BASKETS, BURLAP AND/OR TWINE, OR ENTIRE CONTAINER, AND REMOVE FROM THE PLANTING PIT, SCARIFY ROOTS FOR ALL CONTAINERIZED PLANTS 5 GALLONS FOR SMALLER

- 3" LAYER OF MULCH, PER PLANS & NOTES


- BACKFILL PLANTING PIT PER SHRUB PLANTING SPECIFICATIONS WHEN PROVIDED, OR WITH NATIVE SOIL-EXCEPT WHEN IN HEAVY CLAY, MIX AMENDED TOPSOIL FROM A LOCAL SOURCE WITH NATIVE SOII

EXCAVATE PLANTING PIT TO A DEPTH EQUAL TO THE DEPTH OF THE ROOTBALL / CONTAINER MINUS 3" AND A MINIMUM TWICE THE DIAMETER OF THE ROOTBALL / CONTAINER - TILL ALL PLANTING BEDS TO A MINIMUM DEPTH OF 6" THROUGHT

PLACE ROOTBALL ON UNDISTURBED SOIL AND ENSURE PLANT IS PLUMB


# SHRUB PLANTING DETAIL

SCALE: 1" = 1'-0"



#### **GENERAL PLANTING NOTES**

- COORDINATE LOCATION OF ALL UTILITIES (LINES, DUCTS, CONDUITS, SLEEVES, FOOTINGS, ETC.) WITH LOCATIONS OF PROPOSED LANDSCAPE ELEMENTS (FENCE, FOOTINGS, TREE ROOTBALLS, ETC.). CONTRACTOR SHALL REPORT ANY DISCREPANCIES TO OWNERS REPRESENTATIVE PRIOR TO CONTINUING WORK.
- 2. SAVE AND PROTECT ALL EXISTING TREES NOT NOTED TO BE REMOVED.
- REMOVE ALL CONSTRUCTION DEBRIS AND MATERIALS INJURIOUS TO PLANT GROWTH FROM PLANTING PITS AND BEDS PRIOR TO BACKFILLING WITH PLANTING MIX.
- LAWN AREAS SHALL HAVE 6\* MINIMUM DEPTH OF TOPSOIL. TOPSOIL SHALL BE COMPACTED TO 85% MAXIMUM DENSITY AT OPTIMUM MOISTURE CONTENT.
- REFER TO PLANTING DETAILS PLAN FOR AMENDED SOIL DEPTH IN PLANTING BEDS AND SURROUNDING TREES.
- FIELD STAKE PLANTINGS ACCORDING TO PLAN. OWNER'S REPRESENTATIVE SHALL APPROVE ALL PLANT LOCATIONS PRIOR TO INSTALLATION. OWNER RESERVES THE RIGHT TO REVISE PLANTING LAYOUT AT TIME OF INSTALLATION.
- ALL PLANT MATERIALS SHALL BE TRUE TO THEIR SCIENTIFIC NAME AND SIZE AS INDICATED IN THE PLANT SCHEDULE.
- IF DISCREPANCIES EXIST BETWEEN THE NUMBER OF PLANTS DRAWN ON THE PLANTING PLAN AND THE NUMBER OF PLANTS IN THE SCHEDULE, THE PLANTING PLAN SHALL GOVERN.
- OWNER RESERVES THE RIGHT TO REVISE QUANTITIES TO SUIT BUDGET LIMITATIONS, CONTRACTOR'S UNIT BID PRICES SHALL PREVAIL FOR ANY CHANGES IN QUANTITIES.
- 10. ANY PROPOSED SUBSTITUTIONS OF PLANT SPECIES SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, BRANCHING HASIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE, AND ONLY AFTER WRITTEN APPROVAL OF THE OWNER'S REPRESENTATIVE AND OWNER.
- ALL PLANT MATERIALS MUST CONFORM TO AMERICAN STANDARDS FOR NURSERY STOCK (A.N.S.I.), LATEST EDITION PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, WASHINGTON D.C. LARGER SIZED PLANT MATERIALS OF THE SPECIES LISTED MAY BE USED IF THE STOCK CONFORMS TO A.N.S.I.
- 12. ALL PLANT MATERIAL SHALL BE GUARANTEED TO BE IN A LIVE AND HEALTHY GROWING CONDITION FOR ONE FULL GROWING SEASON (ONE YEAR) AFTER FINAL PROJECT ACCEPTANCE OR SHALL BE REPLACED FREE OF CHARGE WITH THE SAME GRADE AND SPECIES. ALL TREES SHALL HAVE A STRONG CENTRAL LEADER.
- CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE DUE TO OPERATIONS, ANY AREAS THAT ARE DISTURBED SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE OWNER.
- PLANTING BED EDGING USE 1/8" x 4" METAL EDGING IN ALL AREAS WHERE PLANTING BED MEETS LAWN AREAS OR WHERE INDICATED, USE 12" METAL SPIKES AS INSTRUCTED BY MANUFACTURER.
- PROVIDE ROCK MULCH, 3-INCH EGG STONE, WITH LANDSCAPE FABRIC, IN ALL PLANTING BEDS TO A 3-INCH MINIMUM DEPTH.
- PROVIDE SHREDDED HARDWOOD MULCH CIRCLE, WITHOUT LANDSCAPE FABRIC, TO A 4-FOOT DIAMETER AROUND ALL TREES OUTSIDE PLANTING BEDS.
- SOD SECTIONS SHALL BE STAKED IN PLACE WITH BIODEGRADABLE SOD STAKES WHEN SLOPE IS STEEPER THAN 5:1 OR WHEN CONDITIONS REQUIRE.
- ALL PLANTS AND TURF TO BE IRRIGATED WITH A PERMANENT, UNDERGROUND IRRIGATION SYSTEM.
- INDICATED QUANTITIES ARE ESTIMATES AND SHOULD BE CONFIRMED BY THE CONTRACTOR/BIDDER.
- INFILTRATION BASIN SHALL RECEIVE EROSION CONTROL PER SWPPP. NO LANDSCAPE FABRIC, NO ROCK MULCH, NO EDGING, AND NO IRRIGATION.



LANDSCAPE EDGING DETAIL



CONSTRUCTION

OR

Ľ

NOT

RELIMINARY

Δ

ONSTRUCTION

Ö

OR

0

Z

**ELIMINARY** 

ĸ

Δ.

EIGHT

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, NC, AND MAY NOT BE USED, COPIED OR DUPLICATED MTHOUT PRIOR WRITTEN CONSENT.

PROJECT

#### **KINDERCARE**

# WEST DES MOINES


	ISSUE SCHEDULE
DATE	DESCRIPTION
11/04/19	CLIENT REVIEW SET
11/13/19	CITY SITE PLAN SUBMITTAL #1
01/13/20	CITY SITE PLAN SUBMITTAL #2
02/17/20	CITY SITE PLAN SUBMITTAL #3
	REVISION SCHEDULE
DATE	DESCRIPTION


PROJECT NO.	19-23523
FILE NAME	23523 C5-LAND
DRAWN BY	ARA
DESIGNED BY	ARA/RJA
REVIEWED BY	RJA/ART
ORIGINAL ISSUE DATE	-/-/-
CLIENT PROJECT NO.	¥)


TITLE


PLANTING SCHEDULE, NOTES, & DETAILS


SHE













CONCRETE SLAB (MIN 4000 PSI)


COMPACTED SUBGRADE





CONCRETE SLAB (MIN 4000 PSI)


AGGREGATE BASE













SYNTHETIC TURF CROSS SECTION

TOP AT INFILL HEIGHT (CONFIRM W/-SYNTHETIC TURF SUPPLIER PRIOR TO INSTALLATION OF NAILER) PLAY STRUCTURE AREA

PLAY STRUCTURE AREA



12" X 6" CONCRETE CURB AND WOOD NAILER AT PLAYGROUND EDGE



FENCE NOTE:

STYLE TO BE AMERISTAR MONTAGE PLUS MAJESTIC STEEL FENCING. SEE MANUFACTURER SPECIFICATIONS FOR ADDITIONAL INFORMATION AND DETAILS.

2-1/2" MAX

CONTRACTOR TO PROVIDE SHOP DRAWING TO LA-E FOR APPROVAL PRIOR TO FABRICATION.

PANIC HARDWARE TO BE PROVIDED WHERE REQUIRED BY CODE.

STEEL FENCE GATE DETAIL

8'-0" OC MAX



CONSTRUCTION

FOR

RELIMINARY NOT

Δ

OR

LON

**PRELIMINARY** 

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

1-1/2" Ø RAIL,

- 2-1/2" Ø 16 GA

POST, TYP.

- 3/4" Ø 17 GA

FENCE BRACKET, TYP

TOP OF CURB

CONCRETE

4000 PSI

FOOTING, MIN

### **KINDERCARE**

## **WEST DES MOINES**

CONSTRUCTION WEST DES MOINES ISSUE SCHEDULE DESCRIPTION FENCE PICKET, REVISION SCHEDULE DESCRIPTION 19-23523 PROJECT NO FILE NAME 23523 CO-DETAILS DESIGNED BY ARA/RJA REVIEWED BY RJA/ART ORIGINAL ISSUE DATE --/--/-CLIENT PROJECT NO. -

**SITE DETAILS** 

SHEET

TITLE

C812

8'-0" OC MAX 2-1/2" MAX -- 1-1/2" Ø RAJL, - 2-1/2" Ø 16 GA POST, TYP. -3/4" Ø 17 GA FENCE PICKET, TYP. BRACKET, TYP. TOP OF CURB. -CONCRETE FOOTING, MIN 4000 PSI

FENCE NOTE:

STYLE TO BE AMERISTAR MONTAGE PLUS MAJESTIC STEEL FENCING, SEE MANUFACTURER SPECIFICATIONS FOR ADDITIONAL INFORMATION AND DETAILS.

CONTRACTOR TO PROVIDE SHOP DRAWING TO LA-E FOR APPROVAL PRIOR TO FABRICATION.

PANIC HARDWARE TO BE PROVIDED WHERE REQUIRED BY CODE.

PERIMETER FENCE CURB SECTION

### FENCE NOTE:

CODE.

STYLE TO BE AMERISTAR MONTAGE PLUS MAJESTIC STEEL FENCING, SEE MANUFACTURER SPECIFICATIONS FOR ADDITIONAL INFORMATION AND DETAILS.

CONTRACTOR TO PROVIDE SHOP DRAWING TO LA-E FOR APPROVAL PRIOR TO FABRICATION. PANIC HARDWARE TO BE

PROVIDED WHERE REQUIRED BY 2-1/2" Ø 16 GA-POST, TYP.

CONCRETE FOOTING, MIN 4000 PSI

(3)

FENCE NOTE:

STYLE TO BE AMERISTAR MONTAGE PLUS MAJESTIC STEEL FENCING, SEE MANUFACTURER SPECIFICATIONS FOR ADDITIONAL INFORMATION AND DETAILS.

CONTRACTOR TO PROVIDE SHOP DRAWING TO LA-E FOR APPROVAL PRIOR TO FABRICATION.


PANIC HARDWARE TO BE PROVIDED WHERE REQUIRED BY CODE

4 STEEL FENCE DETAIL
3/4" = 1'-0"

45° CHAMFER EDGE. TYP, BOTH SIDES TOP OF FOOTING SHALL BE FLUSH-WITH TOP OF SYNTHETIC TURF, CONFIRM SYNTHETIC TURF HEIGHT WITH TURF SUPPLIER PRIOR TO INSTALLATION OF NAILER 2" X 4" PRESSURE TREATED WOOD NAILER SYNTHETIC TURF CROSS SECTION, SEE

PERIMETER FENCE CURB SECTION

12\* MIN\_



#### NOTES:


GRIND EXPOSED FIELD & SHOP WELDS FLUSH WITH ADJACENT SURFACES.
ATTER FARBEACTION, GALVANIZE STRUCTURAL SHAPES AND MISCELLANEOUS TENIS IN ACCORDANCE WITH ASTIVA 123.
REPAIR DAMAGE AS CRATCHED GALVANIZED COATINGS AFTER INSTALLATION GROUT AROUND ALL PIPES ON INSIDE AND OUTSIDE OF MANNEOUS


> Dry storage dopth varies

Well storage depth varies.

13' Varies 1'-0" Min.

1'-0" Mm.







CONSTRUCTION

FOR

PRELIMINARY NOT

CONSTRUCTION

FOR

PRELIMINARY NOT

EIGH1

TOP OF GRATEITOP OF CONCRETE STRUCTURE

GALVANIZED 1/2" STEEL POND SKIMMER GRATE

RIM ELEVATION SHOWN ON PLANS

(SEE STRUCTURE SCHEDULE)

BOTTOM OF GRATEITOP OF STRUCTURE

ELEV = 196.61

6.5" ORIFICE

NYERT = 192.66

4" WOY ORIFICE

WYERT = 191.74

GA'9 BASE SLAB

SECTION B-B

SECTION A-A

Driff four, 5/8 inch diameter holes, 3 inches from bottom of rises pipe and insert two, 84 base in an "X" configuration. Length of bare = D+16 inches

Provide perforation configuration as specified in the confirmat documents.

SUDAS 9040.115

SUDAS Standard Specifications

SEDIMENT BASIN DEWATERING DEVICE (PERFORATED RISER)

A-1A POND OUTLET STRUCTURE

#### THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

### **KINDERCARE**

## WEST DES MOINES


	ISSUE SCHEDULE	
DATE	DESCRIPTION	B
11/04/19	CLIENT REVIEW SET	ARA
11/13/19	CITY SITE PLAN SUBMITTAL #1	ARA
01/13/20	CITY SITE PLAN SUBMITTAL #2	ARA
02/17/20	CITY SITE PLAN SUBMITTAL #3	ARA
	REVISION SCHEDULE	Ŧ
DATE	DESCRIPTION	₽,
PROJEC	T NO. 19-23523	
PROJEC		
	NE 23523 CO-DETAILS	
FILE NAM	ME 23523 CO-DETAILS BY ARA	
FILE NAM	ME 23523 CO-DETAILS BY ARA ED BY ARA/RJA	
FILE NAM DRAWN DESIGNE REVIEW	ME 23523 CO-DETAILS BY ARA ED BY ARA/RJA	


# SITE DETAILS

SHEET

C813

#### Installation Instructions





SAND AND WATER PLAY STRUCTURE

CONSTRUCTION

PRELIMINARY NOT FOR

FOR CONSTRUCTION

PRELIMINARY NOT

EIGHT

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

### **KINDERCARE**


DESCRIPTION
CLIENT REVIEW SET
CITY SITE PLAN SUBMITTAL #1
CITY SITE PLAN SUBMITTAL #2
CITY SITE PLAN SUBMITTAL #3
REVISION SCHEDULE
DESCRIPTION

PROJECT NO. 19-23523 FILE NAME 23523 CO-DETAILS DRAWN BY DESIGNED BY ARA/RJA RJA/ART REVIEWED BY ORIGINAL ISSUE DATE ----CLIENT PROJECT NO.

TITLE

SITE DETAILS


C814



CONC. BLLED (TYP.) Trash Enclosure Front Elevation
Scale: 1/T = 1'-0"

PRE-CAST CONCRETE CAP WADRE EDGE AT BOTH SIDE 6° Ø STEEL PIPE - CONC. HULED


Trash Enclosure Side Elevation
Scale: 1/2' = 1'-0"





Bollard Detail
Scale: 1 1/2" = 1"-0"

2 ADHERE TO ALL LOCAL ORDINANCES AND DESIGN REQUIREMENTS. NORTY ARCHITECT OF ANY DISCORPANCIES









ISG

CONSTRUCTION

PRELIMINARY NOT FOR

CONSTRUCTION

FOR

PRELIMINARY NOT

EIGHT

THIS DOCUMENT IS THE PROPERTY OF I & \$ GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

## **KINDERCARE**

WEST DES MOINES

WEST DES MOINES

	ISSUE SCHEDULE	
DATE	DESCRIPTION	BY
11/04/19	CLIENT REVIEW SET	ARA
11/13/19	CITY SITE PLAN SUBMITTAL #1	ARA
01/13/20	CITY SITE PLAN SUBMITTAL #2	ARA
02/17/20	CITY SITE PLAN SUBMITTAL #3	ARA

REVISION SCHEDULE
ATE DESCRIPTION

PROJECT NO.	19-23523
FILE NAME	23523 C1-SWPPP
DRAWN BY	ARA
DESIGNED BY	ARA/RJA
REVIEWED BY	RJA/ART
ORIGINAL ISSUE DATE	
CLIENT PROJECT NO.	(2)

TITLE

TEMPORARY
EROSION AND
SEDIMENT
CONTROL PLAN

SHEET

## **CONSTRUCTION ACTIVITY NOTES:**

#### **EROSION PREVENTION**

Construction of silt fence and all other erosion control measures shall be complete before other construction activity occurs.

Use phased construction wherever practical and establish turf as soon as possible to minimize sediment transport.

Turf establishment or temporary seeding or mulching of all exposed soil not being actively worked should be immediately initiated once earth disturbing activities have ceased. Temporary cover during construction is incidental.

Pipe outlets must be provided with temporary or permanent energy dissipation within 24 hours after connection to a surface water.

Stabilization of disturbed areas must be initiated immediately whenever any clearing, grading, excavating, or other earth disturbing activities have permanently ceased on any portion of the site or temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days.

#### SEDIMENT CONTROL PRACTICES:

Construction of silt fence and all other erosion control measures shall be complete prior to land disturbing activities occur.

Inlet erosion protection shall be installed and maintained until turf has been established.

The contractor shall be responsible to control erosion from leaving the construction zone. All eroded material that leaves the construction zone shall be collected by the contractor and refurmed to the site at the contractor's expense,

All streets must be swept at the end of each working day and prior to a rain event.

Silt fence or other effective erosion control measures must be installed around the perimeter of any
soil stockpiles, including temporary stockpiles. Stockpiles cannot be placed in surface waters,
including storm water conveyances such as curb and gutter systems, or conduits and ditches.

Perimeter control shall be installed along the back of curb immediately following curb installation at all locations with positive drainage to parking lot and/or streets, and shall remain until stabilization is achieved. This shall be accomplished through the use of silt fence, biorolls, Rock logs, or other methods approved by the Engineer.

#### CONSTRUCTION ACTIVITY NOTES:

#### DEWATERING AND BASIN DRAINING:

Dewater sediment-laden water to sedimentation basins if possible, or use other BMP's prevent erosion and remove sediment when discharging to surface waters. Use appropriate energy dissipation measures on all discharges.

Dewatering practices cannot cause nuisance conditions, erosion or in receiving channels or inundation of wetlands resulting in adverse impacts.

#### POLLUTION PREVENTION:

All solid waste collected from the construction site must be disposed in accordance with all applicable regulations.

All hazardous materials (oil, gasoline, fuel, paint, atc) must be properly stored to prevent spills, leaks or other discharge, storage areas shall provide secondary containment and a hazardous materials spill kit. Storage and disposal of hazardous waste must be in compilance with all applicable regulations.

Equipment maintenance areas must be limited to a defined area of the site. All runoff containing any hazardous material must be properly collected and disposed. No engine degreasing shall be allowed on site.

The contractor is responsible for monitoring air pollution and ensuring it does not exceed levels set by focal, state, or federal regulations. This includes dust created by work being performed on the site. Air pollution and dust control correction is considered incidental to the unit bid prices for which work is being performed. Additional dust control measures may be required by the Engineer.

Concrete washout onsite: All liquid waste generated by concrete washout operations must be contained in a leak-proof containment facility or impermeable liner. The liquid waste must not contact the ground, and there must not be runoff from the concrete washout operations or areas. A sign must be installed adjacent to each washout facility to inform concrete equipment operators to utilize the proper facilities. Protect storm sewers and drainage ways from allowing concrete slurry from concrete operations to discharge

#### INSPECTION AND MAINTENANCE:

The Permittees must routinely inspect the construction site once every seven (7) days during active construction.

All inspections performed during construction must be recorded and records retained with

Contractor is responsible for keeping a record of all rainfall information & erosion control maintenance until final establishment of turf.

All silt fences must be repaired, replaced, or supplemented when they become nonfunctional or the sediment reaches  $\stackrel{1}{\mathcal{E}}$  of the height of the fence

Erosion control, and other BMP's must be replaced, repaired, or supplemented when they reach 50% design load,

#### FINAL STABILIZATION:

The Permittees must ensure final stabilization of the site. The Permittees must submit a notice of termination within 30 days after final stabilization is complete or control has been passed to another owner.


All temporary erosion control measures and BMP's must be removed as part of the final


The storm water permit further defines final stabilization and its requirements.


#### MAINTENANCE SCHEDULE

The following Maintenance Schedule has been provided. The INSPECTOR must perform the inspections, The OPERATOR/CONTRACTOR must perform all needed maintenance. Furthermore, all erosion control feature requiring maintenance may not be listed below. The OPERATOR/CONTRACTOR and INSPECTOR must perform their respective duties on all BMP's that are not listed below as well.

- 1. <u>Construction Entrance</u> The entrance shall be maintained in a condition which will prevent tracking or flow of sediment onto public rights-of-way. This may require periodic top dressing with additional stone or the washing and reworking of existing stone as conditions demand and repair and/or cleanout of any structures used to trap sediment. All materials spilled, dropped, washed, or materials dropped, washed or tracked onto roadways will not be permitted under any circumstances.
- 2. Wattles The maintenance measures are as follows: (2.1) wattles shall be inspected weekly; (2.2) close attention shall be paid to the repair of damagad bales, end runs and undercutting beneath bales; (2.3) necessary repairs to barriers or replacement of wattles shall be accomplished promptly; (2.4) sediment deposits shall be removed after each rainfall, they must be removed when the level of deposition reaches approximately one-half the height of the wattle; and (2.5) any sediment deposits remaining in place after the wattle is no longer required shall be dressed to conform to the existing grade, prepared and seeded.
- Silt Fence The maintenance measures are as follows; (3.1) silt fences shall be inspected weekly, any required repairs shall be made immediately; (3.2) close attention shall be paid to the repair of damaged silt fence resulting from end runs and undercutting; (3.3) should the fabric on a silt fence decompose or become ineffective prior to the end of the expected usable life and the barrier is still necessary, the fabric shall be replaced promptly; (3.4) sediment deposits must be removed when the level of deposition reaches approximately one-half the height of the barrier; and (3.5) any sediment deposits remaining in place after the silt fence is no longer required shall be dressed to conform to the existing grade, prepared and seeded.
- Storm Drain Inlet Protection The maintenance measures are as follows: (4.1)
  structures shall be inspected weekly and repairs made as necessary and (4.2)
  structures shall be removed and the area stabilized when the remaining
  drainage area has been properly stabilized.
- Temporary Seeding Areas which fail to establish vegetative cover adequate to prevent rill erosion will be re-seeded as soon as such areas are identified.
- Demanent Seeding. The maintenance measures are as follows: (10.1) in general, a stand of vegetation cannot be determined to be fully established until it has been maintained for one full year after planning; (10.2) new seedlings shall be supplied with adequate moisture, supply water as needed, especially late in the season, in abnormally hot or dry conditions, or on adverse sites, water applications shall be controlled to prevent excessive runoff; (10.3) inspect all seeded areas for failures and make necessary repairs, replacements, and reseedings within the planting season, if possible; [10.3.a] if stand is inadequate for erosion control, over seed and fertilize using half of the rates originally specified; (10.3.b) if stand is lostly damaged, re-establish following seedited and seeding recommendations; (10.3.c) if stand has less than 40% cover, re-evaluate choice of plant materials and quantities of time and fertilizer, the soil must be tested to determine if acidity or nutrient imbalances are responsible, re-establish the stand following seedbed and seeding recommendations.
- Street Cleaning / Sweeping The maintenance measures are as follows: (13.1) evaluate access points daily for sediment tracking; (13.2) when tracked or spilled sediment is found on paved surfaces, it will be removed daily, during times of heavy track-out, such as during rains, cleaning may be done several times throughout the day; (13.3) all streets shall be swept at the end of each working day and prior to a rain event; (13.4) unknown spills or objects will not be mixed with the sediment; and (13.5) if sediment is mixed with other pollutants, it will be disposed of properly at an authorized landfill.









STRUCTIO

Ž O

0

L

O

Ž

RELIMINAR

Δ

STRUCTION

ZO

Ü

FOR

NOT

**ELIMINARY** 

œ

Δ.

EIGH1

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

#### **KINDERCARE**

## WEST DES MOINES

ISSUE SCHEDULE DESCRIPTION	
DESCRIPTION	
	BY
CLIENT REVIEW SET	ARA
CITY SITE PLAN SUBMITTAL #1	ARA
CITY SITE PLAN SUBMITTAL #2	ARA
CITY SITE PLAN SUBMITTAL #3	ARA
REVISION SCHEDULE	_
DESCRIPTION	BY
r NO. 19-23523	
IE 23523 C1-SWPPP	
BY ARA	
D BY ARA/RJA	
D BY RJA/ART	
LISSUE DATE -/-/	
	CITY SITE PLAN SUBMITTAL #2 CITY SITE PLAN SUBMITTAL #3  REVISION SCHEDULE  DESCRIPTION  INO. 19-23523  IE 23823 C1-SWPPP DY ARA D BY ARAPJA ED BY RJAVART

EROSION & SEDIMENT CONTROL NOTES AND DETAILS

CULCI

