

**CITY OF WEST DES MOINES
STAFF REPORT COMMUNICATION**

Meeting Date: August 23, 2021

ITEM: Platinum Pointe Townhomes, Southwest corner of Bridgewood Boulevard and S. 88th Street – Approve a Site Plan to construct 66 attached townhomes – Hale Development Co., LLC – PPSP-005198-2021

Resolution: Approval of Site Plan

Background: Brad Kuehl with Bishop Engineering, on behalf of the applicant and property owner, Hale Development Co., LLC, requests approval of a Site Plan for the approximately 13.352-acre property located at the southwest corner of Bridgewood Boulevard and S. 88th Street. The applicant proposes to construct 66 attached townhomes.

Staff Review & Comment:

- **Financial Impact:** There is no City funding of this project; however, there is staff time for processing of development application and inspections during construction.
- **History:** Platinum Pointe Townhomes (FNA Whisper Ridge Townhomes) was previously approved in 2015 (SP-002568-2014). No work was done to vest the entitlement and the Preliminary Plat expired in 2016. The Site Plan presented has been reviewed and revised to conform to current codes and standards. The preliminary plat for the development was approved by the City Council on August 16, 2021.
- **Staff Note:** Only the Site Plan of the combined Preliminary Plat/Site Plan application is subject of this approval. As noted, the Preliminary Plat aspect was approved August 16th. The site plan was held from approval in conjunction with the Preliminary Plat to allow staff time to resolve a few remaining architectural issues.
- **Conditions of Approval:** There is one condition of approval related to providing necessary final drawings and reports.
- **Vesting of Entitlement:** Per City Code, entitlement (approval to construct or implement) shall remain in effect so long as substantial site work has progressed beyond grading and completion of structural foundations and twenty-five percent (25%) of the total building area has occurred above grade within twenty-four (24) months of the effective date of the approval, unless a greater time period is authorized at time of the original entitlement, or by approval of an extension of the original entitlement. It is the responsibility of the developer to be aware of this deadline and request an extension of the approval prior to the expiration date.

Outstanding Issues: There are no outstanding issues.

Plan and Zoning Commission Action:

Date: August 23, 2021

Vote:

Recommendation:

Recommendation: Approve the Site Plan subject to the applicant meeting all City Code requirements, and the following conditions of approval:

1. Submit final drawings &/or reports to the satisfaction of the Director of the Department of Development Services or her designee prior to any physical construction activity for the site.

Lead Staff Member: Kara Tragesser, AICP

Approval Meeting Dates:

Plan and Zoning Commission	August 23, 2021
City Council	

Staff Report Reviews:

Plan & Zoning Commission	<input checked="" type="checkbox"/> Development Coordinator (or) <input type="checkbox"/> Director	<input checked="" type="checkbox"/> Legal Department
City Council	<input type="checkbox"/> Director <input type="checkbox"/> Appropriations/Finance	<input type="checkbox"/> Legal Department <input type="checkbox"/> Agenda Acceptance


Publications (if applicable)

Published In:	n/a
Date(s) Published	n/a
Date(s) of Mailed Notices	n/a


Council Subcommittee Review (if applicable)

Subcommittee	Development & Planning
Date Reviewed	6/21/21
Recommendation	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Split

Location Map



PRELIMINARY - NOT FOR CONSTRUCTION



GENERAL NOTES:
1. SEE COVER SHEET FOR LEGAL DESCRIPTION AND VICINITY SKETCH.
2. THIS SITE IS NOT LOCATED IN A SPECIAL FEMA FLOOD HAZARD ZONE.

DEMO NOTES:
1. CONTRACTOR SHALL OBTAIN ANY AND ALL REQUIRED PERMITS.
2. ALL WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE CITY OF WEST DES MOINES, COUNTY OF DALLAS, AND STATE OF IOWA
3. CONTRACTOR SHALL BE REQUIRED TO HAVE ANY AND ALL BURIED UTILITIES MARKED OR EXPOSED IN ADVANCE OF THE WORK.
4. DISPOSE OF ALL DEMOLITION MATERIALS OFF SITE IN A LAWFUL MANNER. INCLUDE DISPOSAL IN THE BASE BID. NO EXTRA PAYMENT WILL BE PAID FOR DISPOSAL.

BENCHMARK:
BURY BOLT ON HYDRANT 188 FEET SOUTH OF BRIDGEWOOD CENTERLINE AND 37 FEET EAST OF 88TH STREET CURB, ELEV. 217.49 (WDM DATUM)
BURY BOLT ON HYDRANT 33 FEET NORTH AND 117 FEET EAST OF THE NORTHWEST CORNER OF SUBJECT PROPERTY, ELEV. 217.35 (WDM DATUM)
BURY BOLT ON HYDRANT 33 FEET NORTH OF THE SOUTHEAST CORNER OF SUBJECT PROPERTY, ELEV. 218.75 (WDM DATUM)

CITY OF WEST DES MOINES BM# 35
STANDARD BENCHMARK MONUMENT, 206 FEET EAST OF THE CENTERLINE OF SOUTH 88TH STREET AND 49 FEET NORTH OF THE CENTERLINE OF MILLS CIVIC PARKWAY.
ELEV. 219.04 WDM DATUM


CITY OF WEST DES MOINES BM# 124
STANDARD BENCHMARK MONUMENT IN THE CENTER OF A 6 FOOT WIDE CONCRETE MEDIAN IN MILLS CIVIC PARKWAY, 169 FEET EAST OF THE WEST END OF THE MEDIAN.
ELEV. 203.65 WDM DATUM

UTILITY NOTE:
THE LOCATION OF THE UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM EXISTING PUBLIC RECORDS AND ARE APPROXIMATE LOCATIONS. THE EXACT LOCATIONS OF ALL UTILITIES MUST BE ASCERTAINED IN THE FIELD. IT SHALL BE THE DUTY OF THE CONTRACTOR TO DETERMINE WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS MAY BE PRESENT.



- UTILITY LEGEND:
SANTARY SEWER MANHOLE
STORM SEWER MANHOLE
SAN - SANITARY SEWER
ST - STORM SEWER
G - GAS LINE
W - WATER LINE
UE - UNDERGROUND ELECTRIC
OE - OVERHEAD ELECTRIC
T - TELEPHONE LINE
TELEPHONE RISER
TELEPHONE MANHOLE
GROUND LIGHT
LIGHT POLE
POWER POLE
TRANSFORMER POLE
ELECTRIC TRANSFORMER
ELECTRIC METER
CLEAN-OUT
INTAKE
SURFACE INTAKE
TRAFFIC SIGNAL MANHOLE
FIRE HYDRANT
WATER VALVE
GAS METER
DENOTES NUMBER OF PARKING STALLS

- SURVEY LEGEND:
SECTION CORNER - FOUND AS NOTED
PROPERTY CORNER - FOUND IN W/ VPC ID #16747
PROPERTY CORNER - PLACED 3/4" IRON PIPE W/ YELLOW PLASTIC CAP ID #9532
M - MEASURED DISTANCE
P - PLATTED DISTANCE
D - DEEDED DISTANCE
P.R.A. - PREVIOUSLY RECORDED AS
R.O.W. - RIGHT-OF-WAY
P.O.C. - POINT OF COMMENCEMENT
P.O.B. - POINT OF BEGINNING







Bishop Engineering
"Planning Your Successful Development"
3501 104th Street
Des Moines, Iowa 50322-3825
Phone: (515) 276-0667 Fax: (515) 276-6217
Civil Engineering & Land Surveying
Established 1959

**PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAT
EXISTING CONDITIONS / DEMO PLAN**

REFERENCE NUMBER:
DRAWN BY: SV, BA
CHECKED BY:
REVISION DATE: 1. LAST REVIEW 2015 2. RESUBMIT 05/30/21 3. RESUBMIT 07/07/21 4. RESUBMIT 07/30/21
PROJECT NUMBER: 210136
SHEET NUMBER: C1.1

PRELIMINARY - NOT FOR CONSTRUCTION



Bishop Engineering
"Planning Your Successful Development"
Civil Engineering & Land Surveying
3501 104th Street
Des Moines, Iowa 50322-3625
Phone (515) 276-0467 Fax (515) 276-0217
Established 1959

PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAT
LAYOUT PLAN

REFERENCE NUMBER:
DRAWN BY:
CHECKED BY:

REVISION DATE:
1. LAST REVIEW 2015
2. RESUBMIT 05/30/21
3. RESUBMIT 07/07/21
4. RESUBMIT 07/30/21


TOWNHOME UNITS:
UNITS ARE ONE STORY WITH BASEMENT.

SPECIAL END UNIT TREATMENT:
UNITS NOTED ON THIS PLAN FOR SPECIAL END UNIT TREATMENT INCLUDE LOTS 1, 21, 22, 27, 28, 39, 40, 42, 43, AND 66. THESE UNITS, REGARDLESS OF STYLE, SHALL HAVE STONE OR MASONRY AS THE STYLE DETAILS WRAP AROUND THE FULL LENGTH OF THE END IN THE SAME MANNER AS PROVIDED ON THE FRONT AND REAR ELEVATIONS. UNIT TYPES SELECTED FOR THE PUBLIC VIEW ENDS INDICATED SHALL BE REVIEWED AND APPROVED BY THE CITY OF WEST DES MOINES DURING THE BUILDING PERMIT PROCESS.

PROJECT NUMBER:
210136

SHEET NUMBER:
C2.1

PRELIMINARY - NOT FOR CONSTRUCTION



SURVEY LEGEND:

- ◆ SECTION CORNER- FOUND AS NOTED
- PROPERTY CORNER- FOUND IR W/ YPC ID #16747
- PROPERTY CORNER- PLACED 3/4" IRON PIPE W/ YELLOW PLASTIC CAP ID #9532
- M MEASURED DISTANCE
- P PLATTED DISTANCE
- D DEEDED DISTANCE
- P.R.A. PREVIOUSLY RECORDED AS
- R.O.W. RIGHT-OF-WAY
- P.O.C. POINT OF COMMENCEMENT
- P.O.B. POINT OF BEGINNING
- (100) STREET ADDRESS

Bishop Engineering
 "Planning Your Successful Development"
 3501 104th Street
 Des Moines, Iowa 50322-3825
 Phone: (515) 276-6067 Fax: (515) 276-0217
 Civil Engineering & Land Surveying
 Established 1959

PLATINUM POINTE TOWNHOMES
 SITE PLAN / PRELIMINARY PLAT


PLAT

REFERENCE NUMBER:
 DRAWN BY:
 SV, BA
 CHECKED BY:

REVISION DATE:
 1. LAST REVIEW 2015
 2. RESUBMIT 05/30/21
 3. RESUBMIT 07/07/21
 4. RESUBMIT 07/30/21

PROJECT NUMBER:
210136
 SHEET NUMBER:
C2.2

PRELIMINARY - NOT FOR CONSTRUCTION



EROSION CONTROL NOTES:

1. INSTALL PERIMETER SILT FENCE AS SHOWN ON PLANS PRIOR TO CONSTRUCTION.
2. INSTALL INTAKE PROTECTION WITH SILT FENCE IMMEDIATELY AFTER STORM SEWER CONSTRUCTION.
3. INSTALL FINISHED PAVING INLET PROTECTION IMMEDIATELY AFTER PAVING IS COMPLETED AROUND INTAKE.
4. SEE SWPPP NARRATIVE FOR COMPLETE EROSION CONTROL MEASURES.

TOPSOIL NOTES:

1. STRIP AND STOCKPILE 6" OF TOPSOIL ON ALL DISTURBED AREAS.
2. RESPREAD TOPSOIL TO 6" DEPTH ON ALL GREEN (NON PAVED AREAS). IMPORT TOPSOIL AS NECESSARY TO ACHIEVE A MINIMUM OF 6" DEPTH IN ALL GREEN AREAS.
3. TOPSOIL IS DEFINED AS: FERTILE, FRIABLE LOAM, CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH, FROM WELL DRAINED SITE FREE FROM FLOODING, NOT IN FROZEN OR MUDDY CONDITIONS; REASONABLY FREE FROM SUBSOIL, CLAY LUMPS, ROOTS, GRASS, WEEDS, STONES LARGER THAN ONE INCH (25 MM) DIAMETER, AND FOREIGN MATTER; ACIDITY RANGE (PH) OF 5.5 TO 7.5; CONTAINING MINIMUM 4 PERCENT AND MAXIMUM 20 PERCENT ORGANIC MATTER.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING ALL TOPSOIL REQUIREMENTS OF NPDES GENERAL PERMIT NO. 2 ARE MET AND SHALL PROVIDE THE CITY OF WEST DES MOINES ENGINEERING DEPARTMENT WITH A WRITTEN VERIFICATION OF MEETING THE MINIMUM TOPSOIL REQUIREMENTS.

SEEDING / SODDING REQUIREMENTS:

1. AS INFRASTRUCTURE IMPROVEMENTS AND FINAL FINISH GRADING ARE COMPLETE, SEED ALL DISTURBED AREAS NOT LIKELY TO BE DISTURBED DURING BUILDING CONSTRUCTION WITH SUDAS PERMANENT LAWN MIXTURE. SEED THE BALANCE OF THE SITE WITH TEMPORARY EROSION CONTROL MIXTURE.
2. AS BUILDINGS, DRIVES, AND WALKS ARE COMPLETE, SOD ALL AREAS DISTURBED BY THE BUILDER ACTIVITIES.
3. MULCH ALL SEEDING AREAS WITH SLOPES EXCEEDING 5:1.
4. STAKE ALL SOD ON AREAS WITH SLOPES EXCEEDING 4:1.

IOWA DNR REQUIREMENTS:

1. OWNER AND CONTRACTOR SHALL COMPLY WITH ALL STIPULATIONS OF THE NPDES GENERAL PERMIT NO. 2.
2. CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AN AS-BUILT SURVEY AND RECORD DRAWINGS OF ALL STORM WATER MANAGEMENT FACILITIES ON SITE. THE RECORDS SHALL INCLUDE CERTIFICATION OF SUBSTANTIAL COMPLIANCE WITH THE APPROVED PLANS AND SPOT ELEVATIONS OF ALL LOCATIONS WHERE OVERLAND FLOWAGE IN EASEMENT CROSSES A PROPERTY LINE OR RIGHT-OF-WAY.

GENERAL NOTES:

1. SEE SUPPLEMENTAL DETAILED STORM WATER POLLUTION PREVENTION PLAN PROVIDED IN THE PROJECT SPECIFICATIONS FOR ALL EROSION CONTROL MEASURES, ADDITIONAL DETAILS, AND ADDITIONAL NOTES. ADDITIONAL NOTES AND MEASURES CALLED OUT ON SWPPP SHALL BE CONSIDERED INCIDENTAL AND INCLUDED IN ORIGINAL BID.
2. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE STATEWIDE URBAN STANDARD SPECIFICATIONS FOR PUBLIC IMPROVEMENTS AND THE LOCAL JURISDICTIONAL GOVERNMENT REQUIREMENTS, CODES, REGULATIONS, ORDINANCES, STANDARDS, POLICIES, AND SPECIAL PROVISIONS.
3. ALL WORK SHALL BE IN ACCORDANCE WITH THE CURRENT O.S.H.A. CODES AND STANDARDS. NOTHING INDICATED ON THESE PLANS SHALL RELIEVE THE CONTRACTOR FROM COMPLYING WITH ANY AND ALL APPROPRIATE SAFETY REGULATIONS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF ALL UTILITIES. ANY DAMAGE TO SAID UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
5. CONTRACTOR SHALL CONTACT THE CITY OF WEST DES MOINES ENGINEERING DEPARTMENT PRIOR TO CONSTRUCTION. CONTRACTOR SHALL GIVE THE PUBLIC WORKS 48 HOURS ADVANCE NOTICE. ALL WORK IN THE RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL JURISDICTIONAL GOVERNMENT. ALL NECESSARY CONSTRUCTION SIGNS AND BARRICADES DURING CONSTRUCTION WILL BE FURNISHED BY THE CONTRACTOR. SIGNS AND BARRICADES MUST BE IN CONFORMANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, STREETS AND HIGHWAYS" AND IN ACCORDANCE WITH THE LOCAL GOVERNMENT REQUIREMENTS.
6. CONTRACTOR SHALL OBTAIN ANY AND ALL NECESSARY PERMITS FROM THE CITY, COUNTY, OR STATE PRIOR TO ANY CONSTRUCTION. A SWPPP AND NPDES PERMIT SHALL BE AVAILABLE ON SITE AT ALL TIMES. THIS SWPPP DRAWING IS ONLY ONE PART OF THE SWPPP WHICH INCLUDES THE NPDES PERMIT, NARRATIVE, GRADING AND UTILITY PLANS, DETAILED CONSTRUCTION PLANS, SITE PLANS, SOILS REPORTS, CONTRACTOR CERTIFICATIONS, INSPECTION REPORTS, AND OTHER SUPPORTING INFORMATION AND DOCUMENTATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING AN ANNOTATED COPY OF THE SWPPP ON SITE DOCUMENTING ANY AND ALL CHANGES, ADDITIONS, AND UPDATES TO THE SWPPP.
7. EROSION CONTROL MEASURES SHOWN AND QUANTITIES LISTED ON THIS PLAN ARE AN ESTIMATION FOR BIDDING PURPOSES ONLY IN ORDER TO ESTABLISH UNIT PRICES. ADDITIONAL MEASURES TO MEET THE REQUIREMENTS OF THE SWPPP AND CHANGING SITE CONDITIONS MAY BE NEEDED IN ORDER TO PREVENT POLLUTION OF THE STORM WATER DISCHARGE FROM THIS SITE. CONTRACTOR SHALL SUBMIT CHANGE ORDERS TO THE OWNER FOR HIS APPROVAL IN ADVANCE OF EXTRA WORK.
8. ALL POLLUTION PREVENTION MEASURES REQUIRED, AS A RESULT OF CONSTRUCTION ACTIVITIES, ARE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL TAKE ALL ACTIONS NECESSARY FOR INSTALLATION OF CONTROL MEASURES FOR COMPLIANCE WITH PERMIT REQUIREMENTS.
9. INSPECTOR SHALL MEET DNR AND EPA REQUIREMENTS FOR ALL INSPECTION INCLUDING BUT NOT LIMITED TO DISTURBED AREAS, TRACK OUT, ENTRANCE, DISCHARGE POINTS AND STORAGE AREAS.
10. MODIFICATIONS TO THE SWPPP SHALL BE IMPLEMENTED WITHIN 7 CALENDAR DAYS FOLLOWING THE INSPECTION.
11. THE INSPECTION REPORTS SHALL INCLUDE THE INSPECTOR'S QUALIFICATIONS.
12. ALL CONTRACTORS SHALL SUBMIT A CONTRACTOR'S CERTIFICATION STATEMENT PRIOR TO BEGINNING WORK AT THE SITE. ALL CERTIFICATIONS SHALL BE INCLUDED IN THE SWPPP.
13. CONTRACTOR SHALL PICK UP ANY DEBRIS SPILLED ONTO THE ADJACENT RIGHT-OF-WAY OR ABUTTING PROPERTIES AS THE RESULT OF THIS CONSTRUCTION PROJECT. PERFORM CLEAN UP IMMEDIATELY. DISPOSE OF ALL DEBRIS OFF SITE IN A LAWFUL MANNER. CONTRACTOR SHALL LIMIT ACCESS TO THE SITE ACROSS STABILIZED AREAS IN ORDER TO LIMIT THE TRACKING OF SITE SOIL ONTO ADJACENT RIGHT-OF-WAY AND PROPERTY. STREETS SHALL BE CLEANED DAILY AT THE CLOSE OF WORK AND PRIOR TO ANY RAIN EVENT.
14. CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PROTECT THE EXISTING LANDSCAPING AND INSURE THE SURVIVAL OF EXISTING TREES AND SHRUBS. REPLACE ALL DAMAGED LANDSCAPING MATERIAL AT NO COST TO THE OWNER.
15. ALL DISTURBED AREAS SHALL BE SEED, FERTILIZED AND MULCHED AS SOON AS POSSIBLE AFTER CONSTRUCTION IS COMPLETE.
16. AS FINAL STABILIZATION IS ACHIEVED, THE CONTRACTOR SHALL REMOVE CONTROL DEVICES AND REPAIR AND STABILIZE AREAS DISTURBED DURING THE REMOVAL PROCESS. REMOVAL IS INCLUDED IN THE UNIT PRICE FOR THE CONTROL DEVICE.
17. PROPOSED PUBLIC SIDEWALK FINAL GRADES SHALL MEET CITY OF WEST DES MOINES REQUIREMENTS FOR PARKING AREA ADJACENT TO STREET, GRADING IN THE PUBLIC RIGHT OF WAY OF 68TH STREET AND ROCKWOOD LANE IS BY OTHERS. FINAL GRADING AS REQUIRED FOR THOSE STREETS AND FOR BRIDGEWOOD BLVD IS INCLUDED IN THIS PLATINUM POINTE TOWNHOMES PROJECT. ALL PUBLIC WALK IMPROVEMENTS SHALL COMPLY WITH PROWAG AND CH.12 OF SUDAS 2013 ED.

UTILITY NOTE:

THE LOCATION OF THE UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM EXISTING PUBLIC RECORDS AND ARE APPROXIMATE LOCATIONS. THE EXACT LOCATIONS OF ALL UTILITIES MUST BE ASCERTAINED IN THE FIELD. IT SHALL BE THE DUTY OF THE CONTRACTOR TO DETERMINE WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS MAY BE PRESENT.



PROPERTY DESCRIPTION:

THE NORTHEAST 1/4 OF THE NORTHEAST 1/4 OF SECTION 15, TOWNSHIP 78 NORTH, RANGE 26 WEST OF THE 5TH P.M., CITY OF WEST DES MOINES, DALLAS COUNTY, IOWA; EXCEPT THE SOUTH 66.00 FEET, THEREOF; AND EXCEPT, WHISPER RIDGE PLAT 1, 2, AND 3, OFFICIAL PLATS NOW INCLUDED IN AND FORMING A PART OF THE CITY OF WEST DES MOINES, DALLAS COUNTY, IOWA. SAID TRACT OF LAND CONTAINS 13.32 ACRES, MORE OR LESS.

ADDRESS:
88TH AND BRIDGEWOOD
WEST DES MOINES, IOWA 50265

OWNER/APPLICANT:
HALE DEVELOPMENT COMPANY LLC
6820 TONI DRIVE
DES MOINES, IA 50313
515-289-1271


STREET CLEANING:
HALE DEVELOPMENT COMPANY LLC

EROSION CONTROL:
TBD
PHONE: TBD


LEGEND:

- PROPOSED DRAINAGE SWALE
- SILT FENCE (TYP)
- STREET ADDRESS
- EXISTING CONTOUR
- PROPOSED CONTOUR
- STABILIZED ENTRANCE 30"X90"-6" DEEP 2" CLEAN CRUSHED ROCK DRIVE ON GEOTEXTILE


214.50 MPE - MINIMUM PROTECTION ELEVATION
ALL WINDOW AND DOOR SILLS SHALL BE PLACED AT OR ABOVE THESE ELEVATIONS UNLESS THEY ARE PROTECTED BY FLOOD PROOFED WINDOW WELLS.




FOUNDATION GRADE DETAIL
NO SCALE




DRAINAGE SWALE DETAIL
NOT TO SCALE




FLOOD PROOF WINDOW WELL DETAIL
NO SCALE




DETAIL OF PCC FLUME
NO SCALE




SITE ENTRANCE DETAIL
NOT TO SCALE




CONCRETE WASH-OUT BAG DETAIL
NOT TO SCALE



INLET PROTECTION DETAIL
NOT TO SCALE



DETAIL OF SILT FENCE AT DITCH OR SWALE



SILT FENCE DETAILS
NOT TO SCALE

COMPLY WITH ALL NOTATIONS AND RECOMMENDATIONS INCLUDED IN THE GEOTECHNICAL REPORT, ABE PN 141461 DATED 12-3-2014



Bishop Engineering
"Planning Your Successful Development"
3501 104th Street
Des Moines, Iowa 50322-3825
Phone: (515) 276-0467 Fax: (515) 276-0217
Civil Engineering & Land Surveying
Established 1959

PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAT
GRADING PLAN / SWPPP

REFERENCE NUMBER:
DRAWN BY:
SV, BA
CHECKED BY:
REVISION DATE:
1. LAST REVIEW 2015
2. RESUBMIT 05/30/21
3. RESUBMIT 07/07/21
4. RESUBMIT 07/30/21

PROJECT NUMBER:
210136
SHEET NUMBER:
C3.1

PRELIMINARY - NOT FOR CONSTRUCTION



PRIVATE WATER MAIN

ITEM	QTY	REQ'D
12" X 8" TAPPING SLEEVE & VALVE	1	REQ'D
BORE & JACK EXISTING STREET CROSSING	60	LF
8" WATER MAIN	1765	LF
8" GATE VALVE	4	REQ'D
8" BEND	6	REQ'D
8" X 8" TEE	1	REQ'D
STD HYDRANT ASSEMBLY	7	REQ'D
1" WATER SERVICE	66	REQ'D

EXISTING UTILITIES:

EXISTING UTILITIES SHOWN WERE GATHERED BY MARKINGS FROM ONE CALL OR REFERENCED OFF UTILITIES COMPANIES PROVIDED MAPS. CONTRACTOR SHALL FIELD VERIFY ALL LOCATIONS.

UTILITY NOTES:

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH CITY OF WEST DES MOINES STANDARD SPECIFICATIONS, CODES, ORDINANCES, REQUIREMENTS, AND REGULATIONS.
- PIPE LENGTHS CALLED OUT ON PLANS INCLUDE FLARED END SECTION, WHERE APPLICABLE.
- PRIVATE SANITARY SEWER, PRIVATE STORM SEWER, AND PUBLIC WATER MAIN ARE SHOWN IN MORE DETAIL ON THE PUBLIC IMPROVEMENT PLANS. REFER TO SEPARATE SET OF PUBLIC IMPROVEMENT PLANS FOR DETAILED CONSTRUCTION REQUIREMENTS. IN THE EVENT OF A DISCREPANCY, THE PUBLIC IMPROVEMENT PLANS SHALL GOVERN.
- ALL STORM SEWER CALLED OUT AS RCP SHALL BE CLASS III RCP. OWNER SHALL BE RESPONSIBLE FOR MAINTAINING THE DETENTION FACILITIES.
- ALL 8" WATER MAIN SHALL HAVE A MINIMUM OF 6" COVER.
- ALL STORM SEWER AND SANITARY SEWER CASTINGS SHALL BE BOLTED DOWN TO STRUCTURE TOP PER SUDAS STANDARDS. COVERS (LIDS/GRATES) SHALL NOT BE BOLTED DOWN TO CASTINGS.
- COORDINATE CITY UTILITY TIE INS AND ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY WITH THE CITY OF WEST DES MOINES ENGINEERING DEPARTMENT.
- ALL HYDRANTS, INCLUDING RELOCATED HYDRANTS, SHALL HAVE STORZ FITTINGS. ADJUST ALL EXISTING UTILITIES TO FINAL GRADE AS REQUIRED INCLUDING BUT NOT LIMITED TO HYDRANTS, VALVES, MANHOLES, INTAKES, SIGNS, HAND HOLES, LIDS, AND CASTINGS.
- ALL FLARED END SECTIONS SHALL INCLUDE FOOTING, JOINT TIES, AND APRON GUARD.
- ALL NEW CONNECTIONS TO EXISTING MANHOLE AND INTAKE STRUCTURES SHALL BE CORE DRILLED. USE LINK SEAL FOR SANITARY CONNECTIONS AND NON-SHRINK MORTAR FOR STORM CONNECTIONS. ANY MANHOLES NEEDING GRADE ADJUSTMENT AND NOT MEETING THE STANDARDS FOR HEIGHT OF ADJUSTING RINGS SHALL BE REBUILT WITH NEW BARREL SECTIONS AS REQUIRED.

SITE LIGHTING:

SITE LIGHTING SHALL BE ACCOMPLISHED WITH COACH LIGHTS. EACH UNIT WILL HAVE TWO EXTERIOR COACH LIGHTS MOUNTED ON EITHER SIDE OF THE GARAGE DOOR.

WEST DES MOINES GENERAL NOTES:


- ALL WATER WORK, PUBLIC OR PRIVATE, SHALL BE DONE IN ACCORDANCE WITH WEST DES MOINES WATER WORKS STANDARD SPECIFICATIONS.
- CONTRACTOR SHALL NOTIFY WEST DES MOINES WATER WORKS AT LEAST ONE WEEK PRIOR TO CONSTRUCTION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION OF WORK OF ALL SUBCONTRACTORS INVOLVED IN THE PROJECT.
- CONTACT BUILDING INSPECTION (515-222-3630) A MINIMUM OF 24 HOURS IN ADVANCE FOR PRIVATE UTILITY INSTALLATION INSPECTIONS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH THE WEST DES MOINES WATER WORKS AND CITY CROSS CONNECTION CONTROL/CONTAINMENT PROVISION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION OF AN APPROVED BACKFLOW PREVENTION ASSEMBLY FOR CONTAINMENT IN ALL NEW CONSTRUCTION. BACKFLOW PREVENTION TO BE INSTALLED PER CITY ORDINANCE 1297, 54-1998. CONTRACTOR SHALL NOTIFY WEST DES MOINES WATER WORKS, RALPH RENTERIA, ENGINEERING TECHNICIAN (515-222-3465) A MINIMUM OF 24 HOURS AFTER INSTALLATION AND TESTING OF ALL BACKFLOW DEVICES TO SCHEDULE FINAL INSPECTION.
- ALL LIGHTS ARE TO BE DOWNCAST CUTOFF VARIETY. WALL PACKS ARE PROHIBITED. THE MAXIMUM ILLUMINATION ALLOWED AT THE PROPERTY LINE IS 1 FOOT-CANDLE.

SOILS:


COMPLY WITH ALL NOTATIONS AND RECOMMENDATIONS INCLUDED IN THE GEOTECHNICAL REPORT, ABE PN 141461 DATED 12-3-2014.




UTILITY NOTE:
THE LOCATION OF THE UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM EXISTING PUBLIC RECORDS AND ARE APPROXIMATE LOCATIONS. THE EXACT LOCATIONS OF ALL UTILITIES MUST BE ASCERTAINED IN THE FIELD. IT SHALL BE THE DUTY OF THE CONTRACTOR TO DETERMINE WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS MAY BE PRESENT.



ENLARGEMENT 1"=20'



FLARED END SECTION FOOTING DETAIL
NOT TO SCALE








OUTLET RESTRICTION DETAIL
NOT TO SCALE

Bishop Engineering
"Planning Your Successful Development"
3501 104th Street
Des Moines, Iowa 50322-3825
Phone: (515) 276-0467 Fax: (515) 276-0217
Civil Engineering & Land Surveying Established 1959

**PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAT
UTILITY PLAN**

REFERENCE NUMBER:
DRAWN BY: SV, BA
CHECKED BY:
REVISION DATE: 1. LAST REVIEW 2015 2. RESUBMIT 05/30/21 3. RESUBMIT 07/07/21 4. RESUBMIT 07/30/21
PROJECT NUMBER: 210136
SHEET NUMBER: C4.1




PRELIMINARY - NOT FOR CONSTRUCTION



Bishop Engineering
 "Planning Your Successful Development"
 3501 104th Street
 Des Moines, Iowa 50322-3825
 Phone: (515) 276-0467 Fax: (515) 276-0217
 Civil Engineering & Land Surveying
 Established 1959

PLATINUM POINTE TOWNHOMES
 SITE PLAN / PRELIMINARY PLAT
PAVING PLAN

REFERENCE NUMBER:
DRAWN BY: SV, BA
CHECKED BY:
REVISION DATE: 1. LAST REVIEW 2015 2. RESUBMIT 05/30/21 3. RESUBMIT 07/07/21 4. RESUBMIT 07/30/21
PROJECT NUMBER: 210136
SHEET NUMBER: C5.1



- LANDSCAPE NOTES:**
- ALL SEEDING & LANDSCAPE PLANTINGS SHALL BE INSTALLED IN ACCORDANCE WITH THE URBAN STANDARD SPECIFICATIONS, UNLESS SPECIFIED OTHERWISE.
 - SEED ALL DISTURBED AREAS WITHIN THE CONTRACT LIMITS, UNLESS NOTED OTHERWISE. SOD/SEED LIMITS SHOWN ON PLAN ARE FOR REFERENCE ONLY. FINAL LIMITS MAY CHANGE BASED ON CONSTRUCTION ACTIVITIES.
 - PLANT QUANTITIES ARE FOR CONTRACTORS CONVENIENCE. THE DRAWING SHALL PREVAIL IF A CONFLICT OCCURS.
 - ALL PLANT MATERIAL SHALL CONFORM TO THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI Z60.1).
 - CONTRACTOR SHALL WARRANT ALL PLANT MATERIAL FOR A PERIOD OF ONE YEAR FROM THE DATE OF INITIAL ACCEPTANCE.
 - FOR WARRANTY PURPOSES, THE DATE OF INITIAL ACCEPTANCE SHALL BE SUBMITTED IN WRITING TO THE OWNER AND/OR OWNER'S REPRESENTATIVE AFTER ALL PLANT MATERIALS HAVE BEEN INSTALLED AND REVIEWED BY OWNER OR OWNER'S REPRESENTATIVE. PLANT MATERIALS WILL ONLY BE ACCEPTED IF THEY ARE IN AN ALIVE AND THRIVING CONDITION.
 - CONDITIONAL ACCEPTANCE OF PLANT MATERIAL MAY BE GIVEN FOR PLANTS INSTALLED IN A DORMANT CONDITION WITH INITIAL ACCEPTANCE OCCURRING THE FOLLOWING SPRING ONCE THEY ARE SHOWN TO BE ALIVE AND THRIVING.
 - IT IS THE CONTRACTORS RESPONSIBILITY TO REMOVE IDENTIFICATION TAGS AND CORDS ON ALL PLANT MATERIAL PRIOR TO THE COMPLETION OF THE CONTRACT. IDENTIFICATION TAGS (INCLUDING SIZING INFORMATION) MUST BE LEFT ON UNTIL AFTER ACCEPTANCE BY OWNER OR OWNER'S REPRESENTATIVE.
 - CONTRACTOR SHALL PLACE SHREDDED HARDWOOD MULCH AROUND ALL TREES, SHRUBS AND GROUND COVER BEDS TO A DEPTH OF 4 INCHES, UNLESS NOTED.
 - STAKING AND GUYING OF TREES SHALL BE AT THE DISCRETION OF THE CONTRACTOR BASED ON CURRENT ACCEPTED NURSERY STANDARDS. GENERALLY, TREES IN LARGE OPEN AREAS SUBJECT TO SIGNIFICANT WIND SHALL BE STAKED. STAKE AND WRAP TREES IMMEDIATELY AFTER PLANTING. CONTRACTOR SHALL ADJUST AND MAINTAIN GUYING TENSION THROUGHOUT THE PLANT ESTABLISHMENT PERIOD. REMOVE ALL STAKES AND GUY WIRES NO MORE THAN ONE YEAR AFTER INSTALLATION.
 - THE LANDSCAPING CONTRACTOR SHALL HAVE ALL UTILITIES LOCATED BEFORE STARTING ANY SITE WORK OR PLANTING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES.
 - NO LANDSCAPE MATERIAL SHALL BE SUBSTITUTED WITHOUT THE AUTHORIZATION OF THE LANDSCAPE ARCHITECT.
 - ALL EDGING SHALL BE DURAEDGE 3/16" STEEL EDGING - COLOR BLACK, OR APPROVED EQUAL.
 - CONTRACTOR SHALL BE RESPONSIBLE MAINTAINING APPROPRIATE LEVEL OF WATERING FOR ALL NEW PLANTS FOR A PERIOD OF 30 DAYS.
 - ALL SHRUB AND PERENNIAL PLANTING BEDS SHALL BE MULCHED WITH 4" THICK SHREDDED HARDWOOD MULCH.
 - ALL BEDS TO RECEIVE GRANULAR PRE-EMERGENT WEED CONTROL BEFORE AND AFTER MULCH IS INSTALLED.

PLANTING SCHEDULE

CODE	QUAN	COMMON NAME	LATIN NAME	SIZE	ROOT	NOTES
AL	7	AMERICAN LINDEN	TILIA AMERICANA	2.5" CAL	B&B	MATCHED SPECIMENS
LP	8	LONDON PLANET TREE	PLATANUS ACERIFOLIA 'BLOODGOOD'	2.5" CAL	B&B	MATCHED SPECIMENS
MM	5	MARSH MAPLE	ACER X FRIESMANNI 'MARSH'	2.5" CAL	B&B	MATCHED SPECIMENS
OC	11	OCTOBER GLORY MAPLE	ACER RUBRUM 'OCTOBER GLORY'	2.5" CAL	B&B	MATCHED SPECIMENS
PE	3	PIONEER ELM	ULMUS X PIONEER	2.5" CAL	B&B	MATCHED SPECIMENS
RO	19	RED OAK	QUERCUS RUBRA	2.5" CAL	B&B	MATCHED SPECIMENS
SO	3	SCARLET OAK	QUERCUS COCCINEA	2.5" CAL	B&B	MATCHED SPECIMENS
SW	4	SWAMP WHITE OAK	QUERCUS BICOLOR	2.5" CAL	B&B	MATCHED SPECIMENS
TT	14	TULIP TREE	LIRIODENDRON TULIPIFERA	2.5" CAL	B&B	MATCHED SPECIMENS
WO	5	WHITE OAK	QUERCUS ALBA	2.5" CAL	B&B	MATCHED SPECIMENS
PF	24	PRAIRIE FIRE CRABAPPLE	MALUS PRAIRIE FIRE	1.5" CAL	B&B	MATCHED SPECIMENS
RB	37	EASTERN REDBUD	CERCIS CANADENSIS	1.5" CAL	B&B	MATCHED SPECIMENS
SB	23	AUTUMN BRILLIANCE SERICEBERRY	AMELANCHIER GRANDIFLORA 'AUTUMN BRILLIANCE'	8" HT	B&B	MATCHED SPECIMENS (CLUMP FORM)
SS	21	SPRING SNOW CRABAPPLE	MALUS 'SPRING SNOW'	1.5" CAL	B&B	MATCHED SPECIMENS
WK	28	WINTER KING HAWTHORN	CRATAEGUS VIRENS 'WINTER KING'	1.5" CAL	B&B	MATCHED SPECIMENS
BH	41	BLACK HILLS SPRUCE	PICEA GLAUCA DENSATA	6"	B&B	FULL FORM TO GROUND
CS	23	COLORADO SPRUCE	PICEA PUNGENS	6"	B&B	FULL FORM TO GROUND
NS	5	NORWAY SPRUCE	PICEA ABIES	6"	B&B	FULL FORM TO GROUND
AC	43	ALPINE CURRANT	RIBES ALPINUM	#6	CONT	FULL FORM - MATCHED
BC	53	BLACK CHOKEBERRY	ARONIA MELANOCARPA	#6	CONT	FULL FORM - MATCHED
FS	120	FRAGRANT SUMAC	RHUS AROMATICA	#6	CONT	FULL FORM - MATCHED
HN	31	HAKURA NISHIKI WILLOW	SAIKU INTEGRALIA HAKURANISHIKI	#6	CONT	FULL FORM - MATCHED
ID	29	ISANT DOGWOOD	CORNUS SERICEA 'ISANT'	#6	CONT	FULL FORM - MATCHED
JV	38	JUDO VIBURNUM	VIBURNUM JUDIC	30"	B&B	FULL FORM - MATCHED
KF	11	KARL FOERSTER FEATHER REED GRASS	CALAMAGROSTIS ACUTIFOLIA 'KARL FOERSTER'	#1	CONT	FULLY ROOTED IN CONTAINER
KR	52	KNOCKOUT ROSE	ROSA X 'RAZAZ'	#6	CONT	FULL FORM - MATCHED
LD	42	LITTLE DEVIL NINEBARK	PHYSCARPUS OPULIFOLIUS 'LITTLE DEVIL'	#3	CONT	FULL FORM - MATCHED
SG	94	SPRING GLORY FORSYTHIA	FORSYTHIA 'SPRING GLORY'	#5	CONT	FULL FORM - MATCHED
VS	4	VAN HOUTTE SPREA	SPREA VANHOUTTEI	#5	CONT	FULL FORM - MATCHED
A.C. SCREENING PLANTS						
DY	120	DENSIFORM YEW	TAXUS MEDIA DENSIFORMIS	#6	CONT	20 NORTH FACING LOCATIONS
AC	120	ALPINE CURRANT	RIBES ALPINUM	#6	CONT	20 SOUTH FACING LOCATIONS
ID	78	ISANT DOGWOOD	CORNUS SERICEA 'ISANT'	#6	CONT	13 EAST FACING LOCATIONS
LD	78	LITTLE DEVIL NINEBARK	PHYSCARPUS OPULIFOLIUS 'LITTLE DEVIL'	#3	CONT	13 EAST FACING LOCATIONS

LANDSCAPE REQUIREMENTS:

OPEN SPACE REQUIREMENTS:

TOTAL SIZE OF LOT	581,616 SF
TOTAL REQUIRED OPEN SPACE (20%)	116,323 SF
TOTAL LANDSCAPE UNITS (1 / 3000 OF OPEN SPACE)	38.8

TOTAL TREES REQUIRED (2 PER LANDSCAPE UNIT) 78
 TOTAL SHRUBS REQUIRED (8 PER LANDSCAPE UNIT) 233
 TOTAL SHRUBS PROVIDED 233

WEST BUFFERYARD


TOTAL LENGTH	958.4'
TOTAL LANDSCAPE UNITS (1 / 35 LINEAR FEET)	27.4
TOTAL TREES REQUIRED PER UNIT (1 X 27.4)	28
TOTAL PROVIDED	28
TOTAL ORNAMENTAL TREES REQUIRED PER UNIT (2 X 27.4)	55
TOTAL PROVIDED	55
TOTAL SHRUBS REQUIRED PER UNIT (8 X 27.4)	195
TOTAL PROVIDED	195

SOUTH BUFFERYARD

TOTAL LENGTH	580.9'
TOTAL LANDSCAPE UNITS (1 / 35 LINEAR FEET)	16.9
TOTAL TREES REQUIRED PER UNIT (1 X 16.9)	17
TOTAL PROVIDED	17
TOTAL ORNAMENTAL TREES REQUIRED PER UNIT (2 X 16.9)	34
TOTAL PROVIDED	34
TOTAL SHRUBS REQUIRED PER UNIT (8 X 16.9)	102
TOTAL PROVIDED	102

EAST BUFFERYARD

TOTAL LENGTH	707.3'
TOTAL LANDSCAPE UNITS (1 / 35 LINEAR FEET)	20.2
TOTAL TREES REQUIRED PER UNIT (1 X 20.2)	21
TOTAL PROVIDED	21
TOTAL ORNAMENTAL TREES REQUIRED PER UNIT (2 X 20.2)	41
TOTAL PROVIDED	41
TOTAL SHRUBS REQUIRED PER UNIT (8 X 20.2)	122
TOTAL PROVIDED	122



Bishop Engineering
"Planning Your Successful Development"

3501 104th Street
Des Moines, Iowa 50322-3625
Phone: (515) 276-0407 Fax: (515) 276-0217
Established 1959
Civil Engineering & Land Surveying

PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAN
LANDSCAPE PLAN

REFERENCE NUMBER:
DRAWN BY:
SV, BA
CHECKED BY:
REVISION DATE:
1. LAST REVIEW 2015
2. RESUBMIT 05/30/21
3. RESUBMIT 07/07/21
4. RESUBMIT 07/30/21

PROJECT NUMBER:
210136
SHEET NUMBER:
C6.1

L:\LAND PROJECTS 2021\210136 - WHISPERING RIDGE - AKA FERRISWHEEL\210136\210136.LANDSCAPING

L:\LAND PROJECTS\2021\0136 - WHISPERING RIDGE - AKA PLYMOUTH PARK PKWY\DWG\LANDSCAPE.DWG



Bishop Engineering
 "Planning Your Successful Development"
 3501 104th Street
 Des Moines, Iowa 50322-3625
 Phone (515) 276-0467 Fax (515) 276-0217
 Civil Engineering & Land Surveying Established 1959

PLATINUM POINTE TOWNHOMES
SITE PLAN / PRELIMINARY PLAT
LANDSCAPE PLAN

REFERENCE NUMBER:	
DRAWN BY:	SV, BA
CHECKED BY:	
REVISION DATE:	
1. LAST REVIEW	2015
2. RESUBMIT	05/30/21
3. RESUBMIT	07/07/21
4. RESUBMIT	07/30/21
PROJECT NUMBER:	210136
SHEET NUMBER:	C6.2



PROJECT NAME:
Platinum Pointe
Waukee, Iowa

OWNER:
Hale Development
6620 N.W. Toni Dr. Des Moines, IA 50313

DRAWING ISSUE INFORMATION:
ISSUE FOR: Project Status
ISSUE DATE: Issue Date

MARK DATE DESCRIPTION

MANAGEMENT INFORMATION:

PROJECT Project Number

PRINCIPAL IN CHARGE: TIM OLSON PROJECT ARCHITECT: JS

DRAWN: JW CHECKED: JS

BY: BY:

© 2021 ETHOS DESIGN GROUP, INC.
THESE DOCUMENTS HAVE BEEN PREPARED SPECIFICALLY FOR THE PROJECT REFERENCED ABOVE. THEY ARE NOT TO BE USED FOR OTHER PROJECTS OR IN LOCATIONS OTHER THAN SPECIFIED WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF ETHOS DESIGN GROUP, INC.

SHEET TITLE:

EXTERIOR ELEVATIONS AND ROOF PLAN

SHEET NO.

A200



	IMAGE	COLOR	MANUFACTURER	ITEM NUMBER
ROOF	ASPHALT SHINGLE		GAF TIMBERLINE 50 YR ARCHITECTURAL	
GUTTER	BLACK		K&M SHEET METAL	KST540
TRIM	BLACK PAINTED		JamesHardie	
SIDING	SHINGLE	COBBLE STONE	JamesHardie	
	LAP	COBBLE STONE	JamesHardie	
	VERTICAL	COBBLE STONE	JamesHardie	
	STONE	HACKET LEDGE TULSA	CENTURION STONE	050-791-15
GARAGE DOOR	BLACK PAINTED		CLOPAY	Clopay's Classic™
FRONT DOOR	BLACK PAINTED			STEEL EXTERIOR DOOR PAINTED

PRELIMINARY NOT FOR CONSTRUCTION



PROJECT NAME:
Platinum Pointe
Waukee, Iowa

OWNER
Hale Development

6620 N.W. Toni Dr. Des Moines, IA 50313

DRAWING ISSUE INFORMATION:
ISSUE FOR: Project Status
ISSUE DATE: Issue Date

MARK DATE DESCRIPTION

MANAGEMENT INFORMATION:

PROJECT Project Number
PRINCIPAL IN CHARGE: TIM OLSON PROJECT ARCHITECT: JS
DRAWN BY: JW CHECKED BY: JS


© 2021 ETHOS DESIGN GROUP, INC.
THESE DOCUMENTS HAVE BEEN PREPARED SPECIFICALLY FOR THE PROJECT REFERENCED ABOVE. THEY ARE NOT TO BE USED FOR OTHER PROJECTS OR IN LOCATIONS OTHER THAN SPECIFIED WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF ETHOS DESIGN GROUP, INC.

SHEET TITLE:
OPTION 1 EXTERIOR ELEVATIONS

SHEET NO.:

A201


PRELIMINARY NOT FOR CONSTRUCTION




6 FRONT LEFT ELEVATION




5 FRONT RIGHT ELEVATION




4 LEFT ELEVATION
1/8" = 1'-0"



3 RIGHT ELEVATION
1/8" = 1'-0"



2 REAR ELEVATION
1/8" = 1'-0"



1 FRONT ELEVATION
1/8" = 1'-0"

	IMAGE	COLOR	MANUFACTURER	ITEM NUMBER
ROOF	ASPHALT SHINGLE		GAF TIMBERLINE 50 YR ARCHITECTURAL	
GUTTER	BONE WHITE		K&M SHEET METAL	KST540
TRIM	COBBLE STONE		JamesHardie	
SIDING	STUCCO	GRAY SLATE	JamesHardie	
	VERTICAL	GRAY SLATE	JamesHardie	
	STONE	BILTMORE TEXAS WHITE	CENTURION STONE	400-310-10
GARAGE DOOR	WHITE		CLOPAY	Clopay's Classic™
FRONT DOOR	BLACK PAINTED			STEEL EXTERIOR DOOR PAINTED



PROJECT NAME:
Platinum Points
Waukee, Iowa

OWNER:
Hale Development

6620 N.W. Toni Dr. Des Moines, IA 50313

DRAWING ISSUE INFORMATION:
ISSUE FOR : Project Status
ISSUE DATE : Issue Date

MARK DATE DESCRIPTION

MANAGEMENT INFORMATION:

PROJECT Project Number

PRINCIPAL IN CHARGE: TIM OLSON PROJECT ARCHITECT: JS

DRAWN BY: JW CHECKED BY: JS

© 2021 ETHOS DESIGN GROUP, INC.
THESE DOCUMENTS HAVE BEEN PREPARED SPECIFICALLY FOR THE PROJECT REFERENCED ABOVE. THEY ARE NOT TO BE USED FOR OTHER PROJECTS OR IN LOCATIONS OTHER THAN SPECIFIED WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF ETHOS DESIGN GROUP, INC.

SHEET TITLE:

OPTION 2 EXTERIOR ELEVATIONS

SHEET NO.


A202




5 FRONT LEFT ELEVATION




6 FRONT RIGHT ELEVATION




4 LEFT ELEVATION
1/8" = 1'-0"



3 RIGHT ELEVATION
1/8" = 1'-0"



2 REAR ELEVATION
1/8" = 1'-0"



1 FRONT ELEVATION
1/8" = 1'-0"

	IMAGE	COLOR	MANUFACTURER	ITEM NUMBER
ROOF		ASPHALT SHINGLE	GAF TIMBERLINE 50 YR ARCHITECTURAL	
GUTTER		CHARCOAL	K&M SHEET METAL	KST540
TRIM		IRON GRAY	JamesHardie	
SIDING	STUCCO	PEARL GRAY	JamesHardie	
	LAP	PEARL GRAY	JamesHardie	
	VERTICAL	PEARL GRAY	JamesHardie	
	STONE	HACKET LEDGE KY NO BROWN	CENTURION STONE	150-260-15
GARAGE DOOR		GRAY	CLOPAY	Clopay's Classic™
FRONT DOOR		GRAY		STEEL EXTERIOR DOOR PAINTED

PRELIMINARY NOT FOR CONSTRUCTION

**A RESOLUTION OF THE PLAN AND ZONING COMMISSION
NO. PZC-21-073**

WHEREAS, pursuant to the provisions of Title 9, Zoning of the West Des Moines Municipal Code, the applicant and property owner, Hale Development Co., L.L.C, request approval of the Site Plan for the purpose of constructing 66 attached townhomes on the approximately 13.352-acre property generally located at southwest corner of Bridgewood Drive and S. 88th Street as depicted on the location map included in the staff report; and

WHEREAS, the Site Plan complies with the findings stated in the applicable provisions of Title 9, Chapter 1, the Comprehensive Plan and City Code.

NOW THEREFORE, the Plan and Zoning Commission of the City of West Des Moines recommends the City Council approve the Site Plan (SP-005198--2021), subject to compliance with all the conditions of approval as stated in the staff report, including conditions added at the meeting, and attached hereto as Exhibit "A", if applicable.

PASSED AND ADOPTED on August 23, 2021.

Erica Andersen, Chair
Plan and Zoning Commission

I HEREBY CERTIFY that the foregoing resolution was duly adopted by the Plan and Zoning Commission of the City of West Des Moines, Iowa, at a regular meeting on August 23, 2021, by the following vote:

AYES:

NAYS:

ABSTENTIONS:

ABSENT:

ATTEST:

Recording Secretary